WASHINGTON STATE DEPARTMENT OF ECOLOGY POST OFFICE BOX 47600 OLYMPIA, WASHINGTON 98504-7600

1

1

3 4

1

2

IN THE MATTER OF	

Sierra Pacific Industries 301 Hagara Street Aberdeen, Washington 98520 Sierra Pacific Industries PO Box 496028 Redding, California 96049 NO. PSD-02-02

FINAL APPROVAL OF PSD APPLICATION

5 6

12

- Pursuant to the United States Environmental Protection Agency (EPA) regulations for the
- 7 Prevention of Significant Deterioration (PSD) set forth in Title 40, Code of Federal Regulations,
- 8 Part 52, regulations set forth in the Washington Administrative Code 173-400-141, based upon
- 9 the complete Prevention of Significant Deterioration (PSD) Permit Application submitted by
- 10 Sierra Pacific Industries (SPI) on April 8, 2002, and the technical analysis performed by the
- Department of Ecology (Ecology), Ecology now finds the following:

FINDINGS:

- 1. SPI proposes to install a wood-waste-fired boiler and 20 megawatt (MW) steam turbine to operate in conjunction with the SPI lumber mill located 2.5 kilometers (km) due east of the Aberdeen, Washington city limits, directly east across the river from South Aberdeen, Washington, and about 100 meters west of the community of Junction City.
- 2. SPI is located within a Class II area that is currently designated in attainment or unclassified for all national and state air quality standards (NAAQS).
- The site is 55 km from the nearest Class I Area, Olympic National Park, and beyond 100 km,
 but within 270 km of eight other Class I areas (Alpine Lakes Wilderness, Glacier Peak
 Wilderness, Goat Rocks Wilderness, Mt. Adams Wilderness, Mt. Hood Wilderness, Mt.
- Rainier National Park, North Cascades National Park and Pasayten Wilderness).
- 4. The site is more than 100 km from the U.S. Canadian border, and is not subject to the
 United States Canada, or State of Washington Canada agreements of 1991 and 1992/94,
 respectively.
- 26 5. This project consists of:
- 5.1 Installing one wood-waste-fired boiler with a capacity of about 310 million British thermal units per hour (MMBtu/hr) heat input, and
- 5.2 Installing a steam-driven electricity-generating turbine with an output capacity of 20 megawatt (MW).
- 6. This project is subject to New Source Performance Standards (NSPS): 40 CFR Subpart Db (Standards of Performance for Industrial-Commercial-Institutional Steam Generating Units).

- 7. The emissions of all air pollutants from the proposed modification are subject to review
- under Chapter 173-400 WAC, Chapter 173-460 WAC and the regulations of the Olympic
- Regional Clean Air Authority (ORCAA 2940 Limited Lane NW, Olympia, WA 98502).
- Chapter 173-400 WAC includes provision for PSD review (WAC 173-400-141). This permit
- 37 considers only PSD applicable issues. All other air quality related Notice of Construction
- approval issues are subject to the ORCAA authority.
- 8. SPI will have the potential to emit more than 250 tons per year (TPY) of any one pollutant that is subject to the federal Clean Air Act. This qualifies SPI as a major stationary source as defined in federal regulations 40 CFR Part 52.21(b)(1)(i)(b).
- 42 9. As a result of this project, SPI's net increases in potential to emit pollutants subject to PSD
 43 review and greater than the respective PSD significant emission rates (SER) will be:
 - 9.1 135 TPY for nitrogen oxides (NO_X): The SER for NO_X is 40 TPY.
- 45 9.2 475 TPY for carbon monoxide (CO): The SER for CO is 100 TPY.
- 9.3 27 TPY of particulate matter (PM), all assumed to be under 10 microns in diameter (PM₁₀): The SERs for PM and PM₁₀ are 25 TPY and 15 TPY, respectively.
- 48 10. Because SPI will be a major stationary source, will have net emissions increases for NO_X,
- CO, and PM/PM₁₀ in excess of each respective PSD SER, and intends to locate in an area
- that is in attainment/unclassified for the NAAQS for NO_X, CO and PM/PM₁₀. The project
- 51 qualifies as a major new source under federal regulations [40 CFR 52.21(b)(1)(i)(b), 40 CFR
- 52.21(b)(3)(i)(a) and 40 CFR 52.21(b)(23)(i)]. As a result, the project is subject to PSD
- 53 review.

44

65

- 54 11. Other than NO_X, CO and PM/PM₁₀, SPI's net emissions increases of all pollutants subject to
- regulation under the federal Clean Air Act are below the significance levels specified in 40
- 56 CFR 52.21(b)(23)(i). As a result, they are not subject to inclusion in this PSD permit.
- 57 12. SPI submitted the PSD permit application on April 9, 2002. On May 8, 2002, Ecology
- notified SPI that the permit application was determined to be complete. On July 22, 2002,
- Ecology released the draft permit for public review and comment. On October 9, 2002,
- Ecology held a hearing on the proposed permit. Ecology has determined that no comments
- received during the review period or at the hearing justify a change to the approval
- 62 conditions of the draft permit.
- 63 13. Best Available Control Technology (BACT) determinations:
- 64 13.1 For NO_X emissions:
 - 13.1.1 Use of a spreader stoker boiler design.
- 66 13.1.2 Selective noncatalytic reduction (SNCR).
- 67 13.1.3 A short-term (24 hour average) limit of 0.15 pounds NO_X per million British 68 thermal units (lb NO_X/MMBtu) and a limit for any twelve consecutive month 69 period equivalent to not greater than 0.1 lb NO_X/MMBtu on an 8,760 hrs/yr
- 70 basis (135 TPY).

- 71 13.2 For CO emissions:
- 72 13.2.1 Good combustion practice, and
- 73 13.2.2 An emission limit of 0.35 pounds CO per million British thermal units (lb CO/MMBtu) on an hourly average basis.
- 75 13.3 For PM₁₀ emissions:
- 76 13.3.1 Use of an dry electrostatic precipitator (ESP), and
- 77 13.3.2 An emission limit of 0.02 pounds PM₁₀ per million British thermal units (lb PM₁₀/MMBtu) on a 24 hour average basis. This converts to 0.01 grains per dry standard cubic foot of combustion exhaust gas.
- 80 14. Allowable emissions will not cause or contribute to air pollution in violation of:
- 81 14.1 Any NAAQS.

83

82 14.2 NAAQS and PSD increment consumption:

Pollutant	Modeled Increment Consumption, Class I area, micrograms per cubic meter (µgrams/m³)	Class I area Allowable Increment Consumption, µgrams/m³	Modeled Increment Consumption, Class II area, μgrams/m ³	Class II area Allowable Increment Consumption, µgrams/m³	Modeled Ambient Concentration, including background, µgrams/m³	NAAQS, µgrams/m³
NO ₂ , annual average	0.004 All NO _x as NO ₂	2.5	4.1	25	17.9	100
CO, 1 hour average	Not applicable (N/A)	N/A	401	N/A	N/A	10,000
CO, 8 hour average	N/A	N/A	228	N/A	N/A	35,000
PM ₁₀ , 24 hour average	0.036	10	29.5	30	104	150
PM ₁₀ , annual average	0.002	5	11.7	17	12.1	50

89

90

91

94

95

96

97

98

99

104105

106

- 85 15. Allowable emissions will not cause a significant visibility impact in:
- 15.1 The surrounding Class I areas: The highest modeled impact was a 2.2% degradation which occurred in Olympic National Park in mid-autumn. Federal land manager guidance considers this to be below the "concern" threshold.
 - 15.2 Nearby Class II wilderness and scenic areas: The highest modeled impact was a 1.2% degradation in the Columbia River Gorge National Scenic Area in mid-spring. Federal land manager guidance considers this to be below the "concern" threshold.
- 92 16. Ambient impact analysis indicates that there will be no significant pollutant deposition on soils and vegetation in the Class I or Class II areas.
 - 16.1 Modeled emissions ambient impact levels are substantially below all secondary NAAQS. This indicates a low likelihood of negative impact on Class II area flora and fauna. No sensitive species have been identified.
 - 16.2 The highest modeled nitrogen deposition in the surrounding Class I areas is 0.0025 kilograms per hectare per year. This is less than 50% of the "concern" threshold in federal land manager guidance.
- 17. No significant effect on industrial, commercial or residential growth in the Aberdeen, Washington area is anticipated as a result of this project.
- 102 18. Ecology finds that all requirements for PSD have been satisfied. Approval of the PSD application is granted subject to the following conditions.

APPROVAL CONDITIONS:

- 107 1. The wood-waste-fired boiler may burn natural gas in the wood-waste-fired boiler:
- 1.1 To ignite the wood-waste fuel, and
- 109 1.2 To maintain good combustion.
- 1.3 SPI shall maintain records of the times and quantity of natural gas used in the woodwaste-fired boiler in accordance with Condition 7.4.
- 112 2. NO_x emissions from the wood-waste-fired boiler exhaust stack:
- 113 2.1 Are limited to not greater than 0.15 lb NO_X/MMBtu on a 24 hour average basis based on heat input value of the fuel.
- 115 2.2 Are limited in any twelve consecutive month period:
- 116 2.2.1 To not greater than 135 tons NO_X emissions.
- 117 2.2.2 An average of 0.10 lb NO_X/MMBtu based on heat input value of the fuel.

118	2.3	SPI wi	Il demonstrate initial compliance with Condition 2.1:
119 120 121		2.3.1	Within 60 days of achieving the maximum firing rate at which the wood-waste-fired boiler will be operated, but not later than 180 days after initial startup, SPI will conduct a compliance test.
122 123 124		2.3.2	The compliance test will use a continuous emission monitoring system (CEMS) that measures and records NO_X emissions from the wood-waste-fired boiler exhaust stack.
125		2.3.3	The CEMS will meet the requirements of Condition 5.1.
126 127		2.3.4	For the compliance test, NO_X emissions from the waste-wood-fired boiler are continuously monitored.
128			2.3.4.1 For not less than 24 consecutive boiler operating hours.
129			2.3.4.2 At an average firing rate of not less than 90 percent of rated capacity.
130 131 132		2.3.5	Compliance will be determined from the arithmetic mean of the NO_X emissions data in $lb\ NO_X/MMBtu$ monitored pursuant to Condition 2.3.4, using a continuous 24 hour period of the compliance test.
133 134		2.3.6	SPI will submit a test plan to Ecology and ORCAA for approval at least 30-days prior to initial performance testing.
135	2.4	SPI wi	Il demonstrate initial compliance with Condition 2.2:
136 137 138		2.4.1	Within 60 days of achieving the maximum firing rate at which the wood-waste-fired boiler will be operated, but not later than 180 days after initial startup, SPI will conduct a compliance test.
139 140		2.4.2	The compliance test will use a CEMS that measures and records NO_X emissions from the wood-waste-fired boiler exhaust stack.
141		2.4.3	The CEMS will meet the requirements of Condition 5.1.
142 143		2.4.4	For the compliance test, NO_X emissions from the waste-wood-fired boiler are continuously monitored for 30 successive boiler operating days.
144 145		2.4.5	Initial compliance will be determined from the arithmetic mean of the NO_X emissions data monitored pursuant to Condition 2.4.4.
146 147			2.4.5.1 Mass emission rates will be determined using the appropriate procedures outlined in 40 CFR part 60 Appendix A Method 19.
148 149			2.4.5.2 An equivalent mass emission rate calculation method may be used if approved in advance by Ecology.
150 151		2.4.6	SPI will submit a test plan to Ecology and ORCAA for approval at least 30-days prior to initial performance testing.
152	2.5	SPI wi	ll monitor continuing compliance with Condition 2.1:
153 154		2.5.1	Following the date the initial performance test in Condition 2.3 is completed, or is required to be complete, whichever date comes first.

155 156			2.5.2	The limit in Condition 2.1 will apply during all periods of operation of the wood-waste-fired boiler.
157 158			2.5.3	Continuous compliance will be monitored by a CEMS that measures and records NO _X emissions from the wood-waste-fired boiler exhaust stack.
159			2.5.4	The CEMS will meet the requirements of Condition 5.1.
160 161 162			2.5.5	Compliance will be determined from the arithmetic mean of each 24 continuous hours of NO_X emissions data in $lb\ NO_X/MMBtu$ monitored pursuant to Condition 2.5.3.
163		2.6	SPI w	ill monitor continuing compliance with Condition 2.2:
164 165			2.6.1	Following the date the initial performance test in Condition 2.4 is completed, or is required to be complete, whichever date comes first.
166 167			2.6.2	Emissions during all periods of operation will be included in monitoring compliance with Condition 2.2.
168 169			2.6.3	Continuous compliance will be monitored by a CEMS that measures and records NO_X emissions from the wood-waste-fired boiler exhaust stack.
170			2.6.4	The CEMS will meet the requirements of Condition 5.1.
171 172			2.6.5	Continuous compliance will be monitored from the arithmetic mean of the NO_X emissions data monitored pursuant to Condition 2.6.3.
173 174				2.6.5.1 Mass emission rates will be determined using the appropriate procedures outlined in 40 CFR part 60 Appendix A Method 19.
175 176				2.6.5.2 An equivalent mass emission rate calculation method may be used if approved in advance by Ecology.
177	3.	CO	emissio	ns from the wood-waste-fired boiler exhaust stack:
178		3.1	CO en	nissions are limited to:
179			3.1.1	On a 1-hour average basis, except during startup or shutdown.
180				3.1.1.1 Not greater than 1,200 ppmdv @ 12 % CO ₂ .
181				3.1.1.2 Not greater than 434 pounds per hour (lb/hr).
182			3.1.2	On an 8-hour average basis, including startup and shutdown.
183				3.1.2.1 Not greater than 600 ppmdv @ 12 % CO ₂ .
184				3.1.2.2 Not greater than 217 lb/hr.
185			3.1.3	On a 24-hour average basis, including startup and shutdown.
186				$3.1.3.1$ Not greater than 300 ppmdv @ 12 % CO_2 .
187				3.1.3.2 Not greater than 108 lb/hr.
188 189			3.1.4	During startup or shutdown of the wood-waste-fired boiler, CO emissions are limited to not greater than 1,500 ppmdv @ 12 % CO ₂ on a 1-hour average basis.

190 191 192			3.1.4.1 Startup commences from a shutdown condition when an ignition flame is first applied to the waste-wood mass in the boiler, and ends when stable burning is established under good combustion practice.
193 194			3.1.4.2 Shutdown commences upon cessation of feed of waste-wood to the boiler, and ends when there is no longer ignited fuel in the boiler.
195 196			3.1.4.3 Neither startup nor shutdown shall exceed a 4-hour continuous period.
197	3.2	SPI w	ill demonstrate initial compliance with Conditions 3.1.1 and 3.1.2:
198 199 200		3.2.1	Within 60 days of achieving the maximum firing rate at which the wood-waste-fired boiler will be operated, but not later than 180 days after initial startup, SPI will have a compliance test conducted by an independent testing vendor.
201 202		3.2.2	The compliance test shall be performed after each installed CEMS has satisfied all required performance demonstration requirements under 40 CFR 60.13(c).
203 204		3.2.3	The wood-waste-fired boiler is to be operated at an average firing rate of not less than 90 percent of rated capacity during the compliance test.
205		3.2.4	Compliance will be determined by EPA Reference Method 10.
206 207			3.2.4.1 Compliance will be demonstrated from the arithmetic mean of not less than three 1-hour test samples.
208 209 210			3.2.4.2 The non-dispersive infrared analyzer must have performance specifications allowing a minimum detectable sensitivity appropriate to the CO concentration limits specified in this condition.
211 212			3.2.4.3 The span and linearity calibration gas concentrations in Method 10 will be appropriate to the CO concentration limits specified in this condition.
213 214			3.2.4.4 Equivalent concentration test methods may be used if approved in advance by Ecology.
215 216 217			3.2.4.5 Mass emission rates will be determined using the appropriate procedures outlined in 40 CFR part 60 Appendix A Method 19 with indicated calculations modified to be applicable to CO.
218 219			3.2.4.6 An equivalent mass emission rate calculation method may be used if approved in advance by Ecology.
220 221		3.2.5	SPI will submit a test plan to Ecology and ORCAA for approval at least 30 days prior to initial performance testing.
222	3.3	SPI w	ill demonstrate initial compliance with Conditions 3.1.3:
223 224 225		3.3.1	Within 60 days of achieving the maximum firing rate at which the wood-waste-fired boiler will be operated, but not later than 180 days after initial startup, SPI will conduct a compliance test.
226 227		3.3.2	The compliance test will use a CEMS that measures and records CO emissions from the wood-waste-fired boiler exhaust stack.

228			3.3.3	The CEMS will meet the requirements of Condition 5.2.		
229 230			3.3.4	For the compliance test for Condition 3.1.3, CO emissions from the wastewood-fired boiler are continuously monitored.		
231				3.3.4.1 For not less than 24 consecutive boiler operating hours.		
232				3.3.4.2 At an average firing rate of not less than 90 percent of rated capacity.		
233 234			3.3.5	Initial compliance for Condition 3.1.3 will be determined from the arithmetic mean of the CO emissions data monitored pursuant to Condition 3.3.4.		
235 236 237				3.3.5.1 Mass emission rates will be determined using the appropriate procedures outlined in 40 CFR part 60 Appendix A Method 19 with indicated calculations modified to be applicable to CO.		
238 239				3.3.5.2 An equivalent mass emission rate calculation method may be used if approved in advance by Ecology.		
240 241			3.3.6	SPI will submit a test plan to Ecology and ORCAA for approval at least 30 days prior to initial performance testing.		
242		3.4	SPI w	ill monitor continuing compliance with Condition 3.1:		
243 244			3.4.1	Following the date the initial performance test in Condition 3.2 is completed, or is required to be complete, whichever date comes first.		
245 246			3.4.2	Continuous compliance will be determined by a CEMS that measures and records CO emissions from the wood-waste-fired boiler exhaust stack.		
247			3.4.3	The CEMS will meet the requirements of Condition 5.2.		
248 249 250			3.4.4	Compliance will be determined from the arithmetic mean of the emissions data for the corresponding averaging period for each CO emission concentration limit in Condition 3.1 monitored pursuant to Condition 3.4.2.		
251 252 253				3.4.4.1 Mass emission rates will be determined using the appropriate procedures outlined in 40 CFR part 60 Appendix A Method 19 with indicated calculations modified to be applicable to CO.		
254 255				3.4.4.2 An equivalent mass emission rate calculation method may be used if approved in advance by Ecology.		
256 257	4.			mission limits from the wood-waste-fired boiler exhaust stack apply to the sum of d condensable fractions, all expressed as PM_{10} :		
258		4.1	All PN	M shall be expressed as PM_{10} .		
259 260		4.2		M_{10} emissions are limited to not greater than 0.02 lb $PM_{10}/MMBtu$ on a 24-hour ge basis based on heat input value of the fuel.		
261 262		4.3		M_{10} emissions are limited to not greater than 27 tons PM_{10} in any twelve cutive month period.		
263		4.4	SPI w	SPI will demonstrate initial compliance with Condition 4.2:		

264 265 266		4.4.1	Within 60 days of achieving the maximum firing rate at which the wood-waste-fired boiler will be operated, but not later than 180 days after initial startup, SPI will have a compliance test conducted by an independent testing vendor.
267 268		4.4.2	The compliance test shall be performed after each installed CEMS has satisfied all required performance demonstration requirements under 40 CFR 60.13(c).
269 270		4.4.3	The wood-waste-fired boiler is to be operated at an average firing rate of not less than 90 percent of rated capacity during the compliance test.
271		4.4.4	Compliance will be determined by EPA Reference Methods 5 and 202.
272273			4.4.4.1 EPA Reference Method 5 will be conducted in the manner prescribed in 40 CFR 60.46b(d).
274 275			4.4.4.2 Compliance will be demonstrated from the arithmetic mean of not less than three <u>2-hour</u> test samples.
276 277			4.4.4.3 The emission rate expressed in lb $PM_{10}/MMBtu$ will be determined using the procedure described in 40 CFR $60.46b(d)(6)$.
278 279		4.4.5	Equivalent concentration test methods may be used if approved in advance by Ecology.
280 281		4.4.6	SPI will submit a test plan to Ecology and ORCAA for approval at least 30 days prior to initial performance testing.
282	4.5	SPI wi	ll demonstrate initial compliance with Condition 4.3:
283 284 285		4.5.1	Within 60 days of achieving the maximum firing rate at which the wood-waste-fired boiler will be operated, but not later than 180 days after initial startup, SPI will conduct a compliance test.
286 287 288		4.5.2	Initial compliance will be determined from the arithmetic mean of the test results from Condition 4.4, converted to TPY PM_{10} , on the basis of design capacity firing rate.
289 290			4.5.2.1 Mass emission rates will be determined using the appropriate procedures outlined in 40 CFR part 60 Appendix A Method 19.
291 292			4.5.2.2 An equivalent mass emission rate calculation method may be used if approved in advance by Ecology.
293	4.6	SPI wi	ll monitor continuing compliance with Condition 4.2:
294 295		4.6.1	SPI will have periodic compliance tests conducted by an independent testing vendor:
296			4.6.1.1 At least once every twelve months,
297 298			4.6.1.2 From the required or actual completion date of the initial performance test in Condition 4.4, whichever date comes first.

335

299 If more than one source test for PM₁₀ is run in a 12-month period, at least one 4.6.2 source test is to coincide with the Relative Accuracy Test Audit required for 300 301 each installed CEMS. 302 4.6.3 Compliance will be determined by EPA Reference Methods 5 and 202. 303 4.6.3.1 EPA Reference Method 5 will be conducted in the manner prescribed in 304 40 CFR 60.46b(d). 305 4.6.3.2 Compliance will be demonstrated from the arithmetic mean of not less 306 than three 2-hour test samples. 307 4.6.3.3 The emission rate expressed in lb PM₁₀/MMBtu will be determined 308 using the procedure described in 40 CFR 60.46b(d)(6). 309 Equivalent concentration test methods may be used if approved in advance by 4.6.4 310 Ecology. 311 4.6.5 SPI will notify Ecology and ORCAA at least 30 days prior to the scheduled 312 performance testing. 313 SPI will monitor continuing compliance with Condition 4.3. 4.7 314 Following the date the initial performance test in Condition 4.4 is completed, or is required to be complete, whichever date comes first. 315 316 4.7.2 Compliance will be monitored from the arithmetic mean of the test results from Condition 4.6 in TPY PM₁₀ based on monthly average firing rates. 317 318 4.7.2.1 Mass emission rates will be determined using the appropriate procedures 319 outlined in 40 CFR Part 60 Appendix A Method 19. 320 4.7.2.2 An equivalent mass emission rate calculation method may be used if 321 approved in advance by Ecology. 322 5. Continuous Emission Monitoring Systems: 323 5.1 Installation, calibration, maintenance and operation of the CEMS for NOx compliance will satisfy the requirements contained in 40 CFR 60.48b(b) through 40 CFR 60.48b(f). 324 325 5.2 CEMS for CO will satisfy the requirements contained in 40 CFR, Part 60, Appendix B, 326 Performance Specification 4 and 40 CFR, Part 60, Appendix F, Quality Assurance Procedures. 327 328 The Relative Accuracy Test Audit required for each installed CEMS will be scheduled 329 to occur during simultaneous test periods. 330 6. SPI will provide safe access and sampling ports for source testing of the waste-wood-fired 331 boiler exhaust stack after the final pollution control device: 332 Safe access will consist of permanently constructed platforms on the stacks. 333 The sampling ports will meet the requirements of 40 CFR, Part 60, Appendix A. 334 Method 1.

6.3 Other arrangements may be acceptable if approved by Ecology prior to installation.

336	7.	SPI v	will not	ify and report to Ecology and ORCAA, and maintain related records as follows:
337 338		7.1	Notific Ecolog	cations and reports will be in written format, or electronic, if approved by gy.
339		7.2	The fo	ollowing notifications shall be submitted to Ecology and ORCAA:
340 341			7.2.1	Commencement of construction of the wood-waste-fired boiler: In accordance with 40 CFR 60.7(a)(1), no later than 30 calendar days after such date.
342 343			7.2.2	Initial startup of the wood-waste-fired boiler: In accordance with 40 CFR 60.7(a)(3), no later than 15 calendar days after such date.
344 345			7.2.3	Completion of the entry into the operation and maintenance manual of the items specified in Condition 8, within fifteen days after such entries were completed.
346 347 348			7.2.4	At the time of submittal of the notification required in Condition 7.2.3, certification by the responsible party for the facility that the relevant equipment was installed consistent with the parameters developed pursuant to Condition 8.
349 350			7.2.5	The date on which the NOx CEMS first demonstrated satisfactory performance pursuant to Condition 5.1, no later than 30 calendar days after such date.
351 352			7.2.6	The date on which the CO CEMS first demonstrated satisfactory performance pursuant to Condition 5.2, no later than 30 calendar days after such date.
353		7.3	The fo	ollowing reports shall be submitted to Ecology and ORCAA:
354 355 356 357			7.3.1	Report results of all initial compliance demonstration source tests on the wood-waste-fired boiler exhaust stack pursuant to Conditions 2.3, 2.4, 3.2, 3.3, 4.4 and 4.5 no later than 45 calendar days after completion of each respective source test.
358 359			7.3.2	Continuing performance monitoring reports required under Condition 7.3.3 shall be submitted for each calendar quarter:
360 361				7.3.2.1 Beginning with the quarter that includes the initial startup of the woodwaste-fired boiler.
362 363				7.3.2.2 Postmarked not later than one calendar month after the close of each respective calendar quarter.
364				7.3.2.3 In the report format approved by Ecology.
365				7.3.2.4 Another reporting schedule may be used if approved by Ecology.
366 367			7.3.3	Continuing performance monitoring reports will include, but not necessarily limited to, the following:
368 369 370				7.3.3.1 Certification by the responsible party for the facility that the relevant equipment was operated and maintained in accordance with the operational parameters and practices developed pursuant to Condition 8.
371				7.3.3.2 Emissions from the wood-waste-fired boiler exhaust stack:

408

372 373			7.3.3.2.1	Pursuant to compliance under Condition 2.1, NO _X emissions (lb/MMBtu) since the last report.		
374 375 376			7.3.3.2.2	Pursuant to compliance under Condition 2.2, the total NO_X mass emissions for the twelve immediately preceding months ending with each month included in the report.		
377 378 379			7.3.3.2.3	Pursuant to compliance under Condition 3.1, CO concentrations and mass emission rates since the last report.		
380 381			7.3.3.2.4	Pursuant to compliance under Condition 4.2, results of any required source tests for PM_{10} since the last report.		
382 383 384			7.3.3.2.5	Pursuant to compliance under Condition 4.3, the total PM_{10} mass emissions for the twelve immediately preceding months ending with each month included in the report.		
385 386			7.3.3.3 The duration span checks	n and nature of any CEMS down-time excluding zero and		
387			7.3.3.4 Results of a	ny CEMS audits or accuracy checks.		
388 389 390 391 392		7.3.4	Each occurrence of NO _X monitored emissions (Conditions 2.1 and 2.2), CO monitored emissions (Condition 3.1) or PM ₁₀ emissions (Conditions 4.2 and 4.3) measured in excess of the limits shall be reported in writing to Ecology and ORCAA after the respective exceedance in accordance with WAC 173-400-107(3) Such reports shall, as a minimum, include:			
393			7.3.4.1 The time of	7.3.4.1 The time of the occurrence.		
394			7.3.4.2 Magnitude of excess from the emission limit.			
395			7.3.4.3 The duration of the excess.			
396			7.3.4.4 The probable cause.			
397			7.3.4.5 Corrective actions taken or planned.			
398			7.3.4.6 Any other a	gency contacted.		
399	7.4	SPI w	rill maintain monitoring, source test, CEM audit tests and process records:			
400		7.4.1	At the Aberdeen facility.			
401		7.4.2	For at least five years.			
402 403		7.4.3	Monitoring and process records that include time and duration of startups and shutdowns of the waste-wood-fired boiler.			
404 405		7.4.4	Records of the times and quantity of natural gas used in the wood-waste-fired boiler.			
406 407		7.4.5	SPI will provide Ecology and ORCAA with the monitoring and process records for any period within the five year archive within ten working days of request.			

8. Operation and maintenance (O&M) manual for the facility:

- Within 90 days of startup, SPI will identify operational parameters and practices for the waste-wood-fired boiler.
- The operational parameters and practices will constitute proper operation relative to compliance with the emission limitation conditions of this permit.
 - 8.3 SPI will include these operational parameters and practices in the waste-wood-fired boiler O&M manual. As a minimum, and to the extent they relate to the emission limitations specified in the conditions of this PSD permit, these will include:
 - 8.3.1 Inspection and maintenance procedures and schedule.
 - 8.3.2 Prescribed acceptable ranges for operation based on manufacturer recommendations.
 - 8.3.3 Section specifying maintenance and calibration of all required monitors used to assure compliance with the terms and conditions of this PSD permit.
 - 8.4 SPI will keep the operational parameters and practices in the waste-wood-fired boiler O&M manual up-to-date to reflect any modifications of the equipment or its operating procedures.
 - 8.5 SPI will keep the waste-wood-fired boiler O&M manual readily available at the facility for review by state, federal and local agencies.
 - 8.6 Within thirty days of request from Ecology, SPI shall submit the O&M manual to Ecology for approval.
- 9. Nothing in this determination will be construed so as to relieve SPI of its obligations under any state, local, or federal laws or regulations.
- 10. Subject to RCW 70.94.200, SPI will permit the Environmental Protection Agency, state and local regulatory personnel access to the source upon request for the purposes of compliance assurance inspections.
- 11. This approval will become invalid if construction of the project is not commenced within eighteen (18) months after receipt of the final approval, or if construction of the facility is discontinued for a period of eighteen (18) months. SPI may extend the 18-month period upon satisfactorily showing that an extension is justified, pursuant to 40 C.F.R. 52.21(r)(2) and applicable EPA guidance.

439 Reviewed by:

441

440

438

413

414 415

416

417

418

419

420

421

422

423

424

425

426

427

442

446

Hernard Brady, P.E.

444 Technical, Information, and Engine

445 Air Quality Program

Washington State Department of Ecolog

DATE: 10-17-02

	Draft PSD Permit Sierra Pacific Industries Aberdeen, WA PSD-02-02	
447		
448	Approved by:	
449		
450		
451	Mary E. Brong	DATE: 17 October 2002
452	Mary E Burg	
453	Program Manager, Air Quality Program	
454	Washington State Department of Ecology	
455		