

PART III UNIT-SPECIFIC CONDITIONS FOR FINAL STATUS OPERATIONS

OPERATING UNIT 11

Integrated Disposal Facility

Chapter 4.0

Process Information

5	4.0	PROCESS INFORMATION [D]	Part III.11.4.1
6			
7	4.1	CONTAINERS [D-1]	Part III.11.4.1
8	4.1.1	Description of Containers [D-1a, D-1b, and D-1c]	Part III.11.4.1
9			
10	4.2	LEACHATE COLLECTION TANKS	Part III.11.4.2
11			
12	4.3	LANDFILLS [D-6].....	Part III.11.4.3
13	4.3.1	List of Wastes [D-6a].....	Part III.11.4.3
14	4.3.2	Liner System Exemption Requests [D-6b]	Part III.11.4.3
15	4.3.3	Liner System, General Items [D-6c].....	Part III.11.4.3
16	4.3.3.1	Liner System Description [D-6c(1)].....	Part III.11.4.3
17	4.3.3.2	Liner System Location Relative to High Water Table [D-6c(2)]	Part III.11.4.7
18	4.3.3.3	Loads on Liner System [D-6c(3)].....	Part III.11.4.7
19	4.3.3.4	Liner System Coverage [D-6c(4)]	Part III.11.4.9
20	4.3.3.5	Liner System Exposure Prevention [D-6c(5)]	Part III.11.4.9
21	4.3.4	Liner System, Foundation [D-6d].....	Part III.11.4.9
22	4.3.4.1	Foundation Description [D-6d(1)].....	Part III.11.4.9
23	4.3.4.2	Subsurface Exploration Data [D-6d(2)].....	Part III.11.4.10
24	4.3.4.3	Laboratory Testing Data [D-6d(3)]	Part III.11.4.10
25	4.3.4.4	Engineering Analyses [D-6d(4)].....	Part III.11.4.10
26	4.3.5	Liner System, Liners [D-6e]	Part III.11.4.12
27	4.3.5.1	Synthetic Liners [D-6e(1)].....	Part III.11.4.12
28	4.3.5.2	Synthetic Liner Compatibility Data [D-6e(1)(a)]	Part III.11.4.12
29	4.3.5.3	Synthetic Liner Strength [D-6e(1)(b)]	Part III.11.4.13
30	4.3.5.4	Synthetic Liner Bedding [D-6e(1)(c)]	Part III.11.4.13
31	4.3.5.5	Soil Liners [D-6e(2)]	Part III.11.4.13
32	4.3.6	Liner System, Leachate Collection and Removal System [D-6f].....	Part III.11.4.15
33	4.3.6.1	System Operation and Design [D-6f(1)].....	Part III.11.4.15
34	4.3.6.2	Equivalent Capacity [D-6f(2)]	Part III.11.4.18
35	4.3.6.3	Grading and Drainage [D-6f(3)].....	Part III.11.4.18
36	4.3.6.4	Maximum Leachate Head [D-6f(4)]	Part III.11.4.18
37	4.3.6.5	System Compatibility [D-6f(5)]	Part III.11.4.18
38	4.3.6.6	System Strength [D-6f(6)]	Part III.11.4.19
39	4.3.6.7	Prevention of Clogging [D-6f(7)].....	Part III.11.4.19
40	4.3.7	Liner System, Construction and Maintenance [D-6g]	Part III.11.4.19
41	4.3.7.1	Material Specifications [D-6g(1)]	Part III.11.4.19
42	4.3.7.2	Construction Specifications [D-6g(2)].....	Part III.11.4.20
43	4.3.7.3	Construction Quality Control Program [D-6g(3)]	Part III.11.4.21
44	4.3.7.4	Maintenance Procedures for Leachate Collection and Removal Systems	
45		[D-6g(4)].....	Part III.11.4.21
46	4.3.7.5	Liner Repairs During Operations [D-6g(5)]	Part III.11.4.21

1	4.3.8	Run-On and Run-Off Control Systems [D-6h].....	Part III.11.4.21
2	4.3.8.1	Run-On Control System [D-6h(1)].....	Part III.11.4.22
3	4.3.8.2	Run-Off Control System [D-6h(2)(a and b) and (3)].....	Part III.11.4.22
4	4.3.8.3	Construction [D-6h(4)].....	Part III.11.4.22
5	4.3.8.4	Maintenance [D-6h(5)].....	Part III.11.4.22
6	4.3.9	Control of Wind Dispersal [D-6i].....	Part III.11.4.22
7	4.3.10	Liquids in Landfills [D-6j].....	Part III.11.4.22
8	4.3.11	Containerized Waste [D-6k].....	Part III.11.4.23

9 **Appendices**

10	4A	DESIGN REPORT – CRITICAL SYSTEMS.....	Part III.11.4A-i
11	4B	CONSTRUCTION QUALITY ASSURANCE PLAN.....	Part III.11.4B-i
12	4C	RESPONSE ACTION PLAN.....	Part III.11.4C-i
13	4D	9090A TEST RESULTS.....	Part III.11.4D-i

14 **Figures**

15	Figure 4.1.	Integrated Disposal Facility Lined Landfill.....	Part III.11.4.23
16	Figure 4.2.	Example of a Typical Liner.....	Part III.11.4.25

4.0 PROCESS INFORMATION [D]

This chapter discusses the processes that will be used to dispose waste in the IDF and includes a discussion of the design and function of the following:

- Container
- Disposal landfill
- Leak detection system
- Leachate collection and removal system
- Secondary leak detection system (Note that the SLDS is not a design requirement of WAC 173-303-665, however DOE is adding the design feature pursuant to its authority under the Atomic Energy Act of 1954 (AEA) and not for the purposes of compliance with the dangerous waste regulations. Therefore information regarding the design, construction and operation of the secondary leak detection system is provided in this application as information only. Pursuant to AEA, DOE has sole and exclusive responsibility and authority to regulate the source, special nuclear and by-product material component of radioactive mixed waste at DOE-owned nuclear facilities. Source, special nuclear and by-product materials, as defined by AEA, are not subject to regulation under RCRA or the Hazardous Waste Management Act, by the State of Washington and are not be subject to State dangerous waste permit, orders, or any other enforceable instrument issued thereunder. DOE recognizes that radionuclide data may be useful in the development and confirmation of geohydrologic conceptual models. Radionuclide data contained herein is therefore provided as a matter of comity so the information may be used for such purposes).

Waste stream compatibility (i.e., compatibility between individual waste streams and compatibility between waste streams and landfill design and construction parameters) will be assessed on a case by case basis. Criteria for assessing and determining compatibility will be identified in either the facility Waste Acceptance Criteria, Waste Analysis Plan, or other protocol or procedure as appropriate (refer to Chapter 3.0, for further discussion of waste stream compatibility).

Process Code S01 (container storage) has been included within this permit application, in the event that storage is required before final disposal (e.g., to support the confirmation process of the waste or cooling of vitrified waste if required). Waste failing the confirmation process (Chapter 3.0) will be identified as off-specification and may require storage prior to disposal. Only off-specification waste or vitrified waste requiring cooling (due to process heat) may be stored in the lined portion of the IDF pending disposition. To maintain operational flexibility, off-specification containers and vitrified waste requiring cooling could be left on the transport vehicles at the IDF until disposal can occur but may be off-loaded into the lined portion of the IDF pending final disposal provided the temperature administrative control limit is not exceeded. Off-specification waste and vitrified waste requiring cooling will be separated from other waste via tape, ropes, chains, or other cordon mechanism.

4.1 CONTAINERS [D-1]

All mixed waste accepted for disposal at the IDF will be packaged in standard containers [U.S. Department of Transportation (DOT) and/or DOE], unless alternate packages are dictated by the size, shape, or form of waste (49 CFR 173) (e.g., metal boxes), and self contained bulk waste.

4.1.1 Description of Containers [D-1a, D-1b, and D-1c]

Mixed waste disposed at the IDF is limited to vitrified low-activity waste (LAW) from the RPP-WTP and DBVS. Additionally, mixed waste generated by IDF operations will be disposed of in IDF.

1 The RPP-WTP and DBVS containers are designed specifically for the vitrified low activity waste form.
2 Nominal RPP-WTP container dimensions will be 122 centimeters base outside dimension,
3 107 centimeters top by 230 centimeters in length, with a wall thickness of 0.357 centimeter with a
4 container volume of 2.55 cubic meters. The DBVS container dimensions are approximately 2.4 meters
5 wide by 3.1 meters tall and 7.3 meters long and a container volume of 54 cubic meters. The vitrified low
6 activity waste will be compatible with the containers, stainless steel for RPP-WTP and carbon steel for
7 DBVS. Before receipt at the IDF, containers will be closed by the generator.

8 Due to the radioactivity and remote handling of the RPP-WTP immobilized waste containers,
9 conventional labeling of the vitrified immobilized waste containers will not be feasible and an alternative
10 to the standard labeling requirements will be used. This alternative labeling approach will use a unique
11 alphanumeric identifier that will be welded onto each immobilized glass waste container. The welded
12 "identifier" will ensure that the number is always legible, will not be removed or damaged during
13 container decontamination, will not be damaged by heat or radiation, and will not degrade over time.

14 The identifier will be welded onto the shoulder and side wall of each immobilized glass container at two
15 locations 180 degrees apart. Characters will be approximately 2 in. high by 1.5 in. wide. The identifier
16 will be formed by welding on stainless steel filler material at the time of container construction. This
17 identifier will be used to track the container from receipt at the RPP-WTP, throughout its subsequent path
18 of shipment and disposal at the IDF.

19 Each identifier will be composed of unique coded alphanumeric characters. This unique alphanumeric
20 identification will be maintained within the plant information network, and will list data pertaining to the
21 waste container including waste numbers, and the major risk(s) associated with the waste.

22 Mixed waste generated through waste operations at IDF will be packaged based on the size of the waste,
23 with the most common container being galvanized or aluminized 208 liter containers.

24 The container packaging and handling for the IDF are designed to maintain containment of the waste,
25 limit storage intrusion, and limit human exposure to mixed waste. Unusual sized containers such as
26 vitrified LAW packages will be handled by using cranes or other appropriate equipment.

27 Operations personnel will inspect each container to confirm appropriate documentation and compliance
28 with the waste acceptance criteria before the container is placed in the IDF (refer to Chapter 3).

29 If containerized mixed waste must be opened (i.e., for confirmation sampling, repackaging, etc.), the
30 container typically would be removed to an onsite treatment and/or storage unit or other approved
31 location before being opened. The container would be sealed before being returned to the IDF.

32 **4.2 LEACHATE COLLECTION TANKS**

33 The aboveground leachate collection tank will support the lined IDF landfill. The leachate collection tank
34 will be operated in accordance with the generator provisions of WAC 173-303-200 and WAC 173-303-
35 640 as referenced by WAC 173-303-200.

36 For informational purposes, the following is provided for an understanding of the operation of the
37 Leachate Collection Tank. Procedures will be written to manage the leachate in accordance with
38 WAC 173-303-200. The presence of leachate in the tank will be detected with instrumentation within the
39 two stilling wells. The level instrument within the first stilling well will monitor the depth of leachate in
40 the tank. A second stilling well will have instrumentation for high-high and low-low alarm set-point
41 trips. The leachate will be removed from the tank using a transfer pump.

1 **4.3 LANDFILLS [D-6]**

2 The following addresses the IDF lined landfill.

3 **4.3.1 List of Wastes [D-6a]**

4 IDF will receive mixed and/or dangerous waste.

5 Waste will be accepted in containers (e.g. drums, boxes, larger containers).

6 Waste streams acceptable at the IDF facility will fall within the range of dangerous waste numbers
7 identified in the Part A form (see chapter 1.0)

8 **4.3.2 Liner System Exemption Requests [D-6b]**

9 This permit application documentation does not seek an exemption to liner system requirements.

10 **4.3.3 Liner System, General Items [D-6c]**

11 This section provides a general description of the liner system to be used for the IDF lined landfill
12 (Figure 4-1).

13 The liner system was designed to prevent migration of leachate out of the lined landfill during the active
14 life of the landfill. The active life will consist of the operational period and the closure/postclosure
15 period. The liner system was designed to meet U.S. Environmental Protection Agency (EPA)
16 requirements, as identified in RCRA Subtitle C requirements for hazardous waste disposal facilities
17 (40 CFR 264), technical guidance documents (e.g., EPA 1985), and WAC-173-303-665. In addition, the
18 liner system will incorporate the following general functional requirements:

- 19 • Range of Operating Conditions--year-round operation, withstand construction, and long-term stresses
- 20 • Degree of Reliability--function safely and effectively throughout operating and closure/postclosure
21 period with minimum maintenance
- 22 • Intended Life--operational phase plus closure/postclosure monitoring phase.

23 **4.3.3.1 Liner System Description [D-6c(1)]**

24 The landfill liner system will comply with WAC 173-303-665 requirements for dangerous waste landfills.
25 Figure 4-2 shows a typical design and includes the following components (from top to bottom).

- 26 • Operations layer: minimum 0.9-meter thick of native soil. This layer will provide a working surface
27 for equipment, protect the liner from mechanical damage, and prevent freezing of the underlying
28 low-hydraulic conductivity soil layer. (Hydraulic conductivity is a measure of how rapidly a material
29 can transmit water and is based on specific ASTM testing requirements.)
- 30 • Leachate collection and removal system (LCRS) will contain a minimum 0.3-meter-thick drainage
31 gravel layer with a hydraulic conductivity of at least 1×10^{-2} centimeter per second (sometimes
32 including perforated drainage pipes). A nonwoven separation geotextile is located between the
33 operations layer and the drainage gravel layer to minimize sediment (fine-soil) migration into the
34 LCRS. A nonwoven cushion geotextile is located between the drainage gravel and the primary
35 geomembrane to protect the primary geomembrane.

1 The LCRS liners will collect and convey leachate to the LCRS sump for removal and will include the
2 following components.

3 • Primary geomembrane liner: this liner will consist of high-density polyethylene (HDPE) because of
4 its excellent resistance to expected chemicals (refer to Chapter 1.0); nominal 60-mil thickness (54-mil
5 minimum), which is textured (to improve stability against sliding). The geomembrane will act as a
6 moisture barrier. Located immediately above the primary geomembrane the LCRS will include a
7 perforated pipe that helps collect and guide water into the leachate collection sump. The perforated
8 pipe is located along the centerline of the cell and provides high-flow path water to the primary
9 collection sump.

10 • Primary geosynthetic clay liner (GCL): the GCL consisting of a high-swelling sodium synthetic mat
11 containing bentonite with a hydraulic conductivity of 1×10^{-8} centimeter per second or less. This
12 layer will act as an additional primary moisture barrier directly under the primary geomembrane.

13 The leak detection system (LDS) is similar to the LCRS except the composite drainage net (CDN)
14 replaces the primary gravel layer, the geosynthetic clay liner (GCL) will be placed directly under the
15 secondary geomembrane liner only under the LDS sump and the perforated pipes will not be needed
16 because very high flow capacities will not be required. The purpose of this system will be to collect any
17 leachate that leaks through the primary liner system and convey the leachate to the LDS sump for
18 removal. The LDS also will serve as a secondary LCRS. The LDS liners will collect and convey leakage
19 to the LDS sump and will include the following components:

20 • Secondary geomembrane liner: same as primary geomembrane liner.

21 • Secondary geosynthetic clay liner: same as primary geosynthetic clay liner.

22 • Admix liner: a minimum 0.9-meter-thick layer of compacted soil/bentonite admixture with a
23 hydraulic conductivity of 1×10^{-7} centimeter per second or less. The bentonite will be high-swelling
24 sodium bentonite. This layer will act as an additional moisture barrier directly under the secondary
25 geosynthetic clay liner in the LDS sump area and the secondary geomembrane outside the LDS sump
26 area.

27 • The secondary leak detection system (SLDS) consists of operations layer type fill for a foundation of
28 the LDS admix layer, drainage gravel with a hydraulic conductivity of at least 1×10^{-2} centimeter per
29 second adjacent to a perforated pipe, a composite drainage net (CDN) and tertiary geomembrane. A
30 nonwoven separation geotextile is located between the operations layer type material and the drainage
31 gravel to minimize sediment (fine-soil) migration into the SLDS piping. The purpose of this system is
32 to provide access to the area immediately below the LDS sump area. The SLDS will collect liquids
33 resulting from construction water and potentially, liquid from other sources. The SLDS liners will
34 convey collected liquids to the SLDS piping for monitoring and/or removal. (Note that the secondary
35 leak detection system is not a design requirement of WAC 173-303-665, however DOE is adding the
36 design feature pursuant to its authority under the Atomic Energy Act of 1954 (AEA) and not for the
37 purposes of compliance with the dangerous waste regulations. Therefore information regarding the
38 design, construction and operation of the secondary leak detection system is provided in this
39 application as information only. Pursuant to AEA, DOE has sole and exclusive responsibility and
40 authority to regulate the source, special nuclear and by-product material component of radioactive
41 mixed waste at DOE-owned nuclear facilities. Source, special nuclear and by-product materials, as
42 defined by AEA, are not subject to regulation under RCRA or the Hazardous Waste Management
43 Act, by the State of Washington and are not be subject to State dangerous waste permit, orders, or any
44 other enforceable instrument issued thereunder. DOE recognizes that radionuclide data may be useful
45 in the development and confirmation of geohydrologic conceptual models. Radionuclide data

1 contained herein is therefore provided as a matter of comity so the information may be used for such
2 purposes).

3 **4.3.3.1.1 Operations Layer**

4 The purpose of the operations layer will be to protect the underlying liner components from damage by
5 equipment during lined landfill construction and operation. This layer also will protect the admix layer
6 from freezing and desiccation cracking.

7 Previous research and experience has shown that desiccation cracks can occur under geomembrane liners
8 when either the liner is not in close contact with the compacted admix or when the liner is subjected to
9 wide temperature fluctuations (Corser and Cranston 1991). The operations layer will act as a weight to
10 keep the geomembrane in contact with the admix, thereby reducing the potential for water vapor to form
11 in an underlying airspace. The operations layer also will act as an insulating layer, together with the dead
12 air space trapped in the underlying drainage layers.

13 The operations layer material typically will consist of onsite granular soil that is reasonably well graded.
14 The material will have a maximum particle size limit of 5.1 centimeters or less, to facilitate protection of
15 the underlying layers.

16 **4.3.3.1.2 Leachate Collection and Removal System**

17 The LCRS will be located below the operations layer and will provide a flow path for the leachate
18 flowing into the LCRS sump. Between the operations layer and the underlying drainage gravel, a
19 geotextile layer will function as a filter separation barrier. The geotextile will prevent migration of fine
20 soil and clogging of the drainage gravel. On the lined landfill floor the drain gravel will be a minimum
21 0.3-meter-thick layer of washed, rounded to subrounded stone, with a hydraulic conductivity of at least
22 1×10^{-2} centimeter per second. In addition, a perforated high-density polyethylene drainage pipe will be
23 placed within the drainage gravel to accelerate leachate transport into the LCRS sump during high
24 precipitation events. On the lined landfill floor the drain gravel layer will be underlain by a geotextile
25 cushion resting on the primary high-density polyethylene geomembrane. The geotextile will provide
26 additional protection for the primary geomembrane on the floor of the landfill.

27 On the lined landfill sideslopes, the LCRS will have a composite drainage net (CDN) layer composed of a
28 geonet (which is a network of HDPE strands, interwoven and bonded to form a panel that provides a
29 drainage pathway for fluids), with a layer of geotextile thermally bonded to each side. This CDN layer
30 will have a transmissivity of at least 3×10^{-5} meters squared per second. The CDN will be used on the
31 sideslopes to avoid problems associated with placement of clean granular material on slopes, thereby
32 minimizing the potential for damaging the underlying liner system.

33 **4.3.3.1.3 Primary Geomembrane Liner**

34 The primary geomembrane liner will act both as an impermeable leachate barrier and as a flow surface,
35 routing leachate to the primary sump. High-density polyethylene will be used because of its high
36 resistance to chemical deterioration. Generally, textured (roughened) geomembrane will be used to
37 maximize shear strength along adjacent interfaces and to reduce the potential for sliding of the liner
38 system.

39 **4.3.3.1.4 Primary Geosynthetic Clay Liner Layer**

40 A primary geosynthetic clay liner (GCL) will consist of a mat of bentonite placed between two
41 geotextiles. The GCL will be installed immediately beneath the primary high-density polyethylene liner
42 on the floor of the lined landfill only. The purpose of this liner will be to provide extra protection in the

1 case of deterioration (such as stress cracking) of the primary geomembrane where operations will
2 continue for several years.

3 The in-place hydraulic conductivity of the GCL will be 1×10^{-8} centimeter per second or less, exceeding
4 the WAC hydraulic conductivity requirement for the secondary soil liners. The upper surface of GCL
5 provides a smooth uniform surface on which to place the overlying geomembrane liner.

6 **4.3.3.1.5 Leak Detection System**

7 The LDS will provide the flow path for leachate flowing into the LDS sump. The following is a
8 description of the system to be used in the IDF landfill.

9 The LDS will have a CDN drainage layer on the floor, and a CDN drainage layer on the sideslopes. The
10 CDN consist of a layer of geotextile thermally bonded to each side of the geonet. These materials and
11 their configuration will be similar to the LCRS described in Section 4.3.3.1.2, except for the absence of a
12 drainage gravel layer and a perforated drainage pipe system on the floor of the lined landfill. The LDS
13 will channel leachate that penetrates the primary liner system through the CDN into the leak detection
14 sump.

15 The LDS serves as a secondary LCRS for the IDF. Leachate collected in the secondary sump will be
16 measured to determine the leakage rate through the primary liner.

17 **4.3.3.1.6 Secondary and Tertiary Geomembrane Liner**

18 The secondary geomembrane liner, located underneath the LDS, will be placed directly against the
19 secondary compacted admix liner, except in the LDS sump area which will include a geosynthetic clay
20 liner between the secondary geomembrane liner and the secondary compacted admix liner. For
21 information only, the tertiary geomembrane liner for the SLDS will be placed directly against subgrade as
22 per 4.3.3.1.8. The secondary and tertiary geomembrane liners will be similar to the primary geomembrane
23 described in Section 4.3.3.1.3. The secondary geosynthetic clay liner material will be similar to the
24 primary geosynthetic clay liner described in Section 4.3.3.1.4.

25 **4.3.3.1.7 Secondary Admix Liner**

26 The secondary admix liner will have a minimum 0.9-meter-thick compacted soil/bentonite admixture
27 located immediately beneath the secondary high-density polyethylene liner, as required by
28 WAC 173-303-665. The secondary admix liner typically will consist of silty sand from local borrow
29 sources mixed with a nominal 12 percent sodium bentonite, by dry weight. The in-place hydraulic
30 conductivity of the admix liner will be 1×10^{-7} centimeter per second or less, consistent with WAC
31 requirements for secondary soil liners. The upper surface of the secondary admix liner will be trimmed to
32 the design grades and tolerances. The surface will be rolled with a smooth steel-drum roller to remove all
33 ridges and irregularities. The result will be a smooth uniform surface on which to place the overlying
34 geomembrane liner.

35 **4.3.3.1.8 Subgrade/Liner System Foundation**

36 The lined landfill in the IDF will be founded in undisturbed native soils or material compacted to at least
37 95 % of a standard proctor maximum density (determined by ASTM D698). The liner system foundation
38 is discussed in further detail in Section 4.3.4.

39 **4.3.3.1.9 Access Ramp**

40 The lined landfill will have an access ramp outside the lined portion of the landfill, minimizing damage to
41 the liner system from vehicle traffic into the lined landfill. As the landfill expands the access ramp will

1 be reconstructed to the south of each expansion in the landfill. The access ramp design could vary as the
2 landfill expands.

3 **4.3.3.1.10 Landfill Expansion**

4 The initial phase of the IDF liner will be complete at the north end of the landfill. As shown in
5 Figure 4-1, construction of the first IDF phase will complete the liner system on the north sideslope and
6 the excavated portions of the landfill floor, east sideslope, and west sideslope. The dashed line of
7 Figure 4-1 across the south edge of the landfill floor denotes the southern extent of the landfill liner. The
8 liner system will be installed to extend approximately 15 meters beyond the estimated toe of slope of the
9 first phase waste placement. This extension will also allow waste haul vehicles to be staged or unloaded
10 over a lined area. Termination detail for the south edge of the liner system is found in Appendix 4A on
11 drawing H-2-830840. The south sideslope of the first phase of IDF is not lined to allow future expansion
12 of the IDF. At the south end of the cells will be a storm water berm/ditch with an infiltration area, which
13 will capture clean runoff from the unlined south sideslope before it runs onto the lined landfill. The
14 landfill floor slopes up 1% from north to south to allow adequate leachate collection capacity for a
15 25 year storm event. Each future liner construction project will connect to the south edge of the
16 previously constructed liner and operations systems and extend the disposal area further to the south.
17 With the expansion of the IDF in subsequent phases, access ramps for the previous phase will be
18 destroyed and new ramps built on the south edge of the landfill.

19 **4.3.3.2 Liner System Location Relative to High Water Table [D-6c(2)]**

20 The water table is located approximately 90 to 100 meters below the ground surface in the IDF. It is
21 anticipated that the deepest point of the liner system will be no greater than 20 meters below ground
22 surface. Consequently, the liner systems will be at least 69 meters above groundwater. The liner systems
23 will not be affected by the water table because of this large elevational difference.

24 **4.3.3.3 Loads on Liner System [D-6c(3)]**

25 The liner system will experience several types of stresses during construction, operation, and
26 closure/postclosure periods. The following sections discuss the types of stress and analytical methods
27 used to design the IDF liners.

28 **4.3.3.3.1 Liner Stress**

29 The geosynthetic liner components will experience some stress particularly during installation and before
30 placing waste in the lined landfill but also during the entire lifecycle. The high-density polyethylene liner
31 will be temperature sensitive, expanding and contracting as liner temperatures increase and decrease.
32 Thermally induced stresses could develop in the liner if deployment and anchoring occur just before a
33 significant decrease in the liner temperature. The operations layer will be sufficiently thick to ensure liner
34 stress remains below the yield strain and stress. Administrative procedures will prevent loading and
35 backfilling of waste exceeding applicable thermal limits due to recent vitrification processes to avoid
36 potential liner damage.

37 The drainage gravel will have the potential to produce localized stress on the geomembrane liner during
38 gravel placement with construction equipment. A geotextile cushion will be placed at the base of the
39 drainage gravel to protect the underlying geomembrane. A puncture analysis was performed to select a
40 sufficiently thick cushion geotextile. This analysis incorporated expected construction vehicle ground
41 pressures and design drainage gravel gradation listed in the construction specifications. If required,
42 engineering controls such as independent foundations will be installed to minimize liner stress involved
43 with large package disposal.

1 On the landfill sideslopes, tension induced by liner-component load transfer is not anticipated, because
2 the liner interface effective shear strength angles will be higher than the sideslope angles. The liner
3 component interface strengths were determined by laboratory direct shear tests. Both static and dynamic
4 stability analyses were performed, using standard methods, design accelerations, and factors of safety.

5 Stress on the geomembrane in the anchor trench also were evaluated during detailed design. Wind uplift
6 and thermal expansion and contraction could cause stress in the geomembrane during construction.
7 However, these stresses will not be a problem, because the stress will be relatively low as compared to the
8 tensile strength of the liner. In addition, these stresses are minimized by using sand bags to control liner
9 position during liner panel placement and welding, as well as keeping the anchor trench open until the
10 liner is stabilized with overlaying fill material. Placement of overlaying fill material is controlled to limit
11 stress buildup in the liner. The stress will not be present after construction, because of the weight and
12 insulating properties of the operations layer.

13 **4.3.3.3.2 Stress Resulting From Operating Equipment**

14 Operations equipment provides a design load case on the IDF liner, which was analyzed as part of the
15 IDF design (refer to Appendix 4-A). The analyses show that the 0.9-meter-thick operations layer will
16 dissipate stress produced by the operating equipment and is sufficient to protect the IDF liner system.

17 **4.3.3.3.3 Stress From Maximum Quantity of Waste, Cover, and Proposed Closure/Postclosure** 18 **Land Use**

19 When the lined landfill is full and the cover system is in place, the liner system will experience a static
20 load from the overlying waste, backfill, and cover materials. No significant increase in stresses on the
21 liner system is anticipated from closure/postclosure land use. The maximum design load of material
22 overlying the liner system includes an allowance for the cover system. Analyses include puncture
23 protection of the geomembrane by the cushion geotextile, and decrease in transmissivity of CDN drainage
24 layers. Materials were specified based on the ability of the materials to perform adequately under
25 closure/postclosure loading conditions.

26 Dynamic stress on the liner system will result primarily from ground accelerations during seismic events.
27 Both static and dynamic analyses were performed on the subgrade and liner components based on the
28 finished configuration of the empty landfill. Under closure/postclosure conditions, the waste, backfill,
29 and cover materials will tend to buttress the liner system, resulting in greater stability relative to the
30 operational phase. All of the analyses verified adequate stability for the IDF.

31 **4.3.3.3.4 Stresses Resulting From Settlement, Subsidence, or Uplift**

32 The subgrade settlement produced by waste loading essentially will be elastic because of the
33 coarse-grained, noncohesive, and drained nature of the soil. The subgrade will rebound during the
34 excavation phase of construction and will settle as the landfill is filled. The compacted admix liner will
35 consolidate under waste loads. The total settlement will be a combination of the subgrade elastic and the
36 admix consolidation settlements. These settlements were analyzed with standard methods during detailed
37 design of the lined landfill. In general, differential settlements will be expected to occur primarily across
38 the lined landfill sideslopes as the thickness of waste decreases from maximum to zero. The geosynthetic
39 liner components were analyzed, the anticipated strains likely will not produce any appreciable stresses in
40 the liner system.

41 The potential for subsidence-induced stress is believed to be negligible based on the following
42 information:

- 43 • The soils underlying the IDF tend to be coarse-grained soils, sands and gravels, in a relatively dense
44 configuration that will not be subject to piping effects that could transport soil resulting in subsidence.

- 1 • The groundwater level will be deep, at least 69.6 meters below the base of the lined landfill, and will
2 not affect bearing soils.
- 3 • No natural voids, or man-made mining or tunneling has been noted. If the groundwater level was
4 lowered substantially and consolidation occurred in the aquifer, local site-specific subsidence would
5 be negligible because of the depth of the groundwater below the lined landfill.

6 The potential for stresses resulting from uplift on the liner system also is expected to be negligible. The
7 seasonal groundwater level is very deep, and higher-elevation perched groundwater likely will not
8 develop because of the absence of aquitards in the coarse-grained Hanford formation underlying the IDF.
9 The coarse-grained nature of the Hanford formation also promotes rapid, primarily vertical, infiltration,
10 which means it is unlikely that infiltration from outside the lined landfill boundary would be transported
11 laterally underneath the landfill liner. Gas pressures similarly are unlikely to develop because of the
12 absence of any organic material that could generate significant subsurface gas (from organic material
13 decomposition) and the coarse-grained, highly permeable sands and gravels underlying the landfill.

14 **4.3.3.5 Internal and External Pressure Gradients**

15 Pressure gradients across the liner caused by liquids or gases will be expected to be negligible. Internal
16 pressures due to liquids will be controlled by the leachate collection and removal system. Because
17 leachate will be removed from the flat 50-foot by 50-foot LCRS sump in a timely manner, there will be
18 minimal liquid head on the liner (less than 30.5 centimeters according to WAC regulations). Gas
19 generated internally is expected to be minimal because waste is inorganic and non-reactive. However any
20 pre-closure internally generated gas will be vented either through the waste or the leachate collection
21 system. The closure cover design will consider gas venting.

22 External pressures on the liner system will be expected to be minimal. Gas pressures will be negligible
23 because the subgrade soil contains no gas producing materials and is highly permeable, readily venting
24 any potential gas to the atmosphere. External pressure from liquids will not be anticipated because of the
25 deep groundwater table and the highly permeable foundation soils.

26 **4.3.3.4 Liner System Coverage [D-6c(4)]**

27 The liner system will cover all soils underlying the lined landfill and extends over the crest of the
28 sideslopes into the anchor trench (Figure 4-2, Detail 3).

29 **4.3.3.5 Liner System Exposure Prevention [D-6c(5)]**

30 No geosynthetic or admix components of the liner system will be exposed to the atmosphere. The
31 minimum 0.9-meter-thick operations layer will cover the entire lined landfill surface. This layer will
32 serve both as a physical protective barrier and as thermal insulation, protecting the admix layer from
33 desiccation and frost damage.

34 Excessive erosion, such as gullyng, will be repaired by replacing the eroded soil. Dust suppression
35 agents will be used to prevent excessive wind erosion on the landfill sideslopes. The dust suppression
36 agents will bind the surface of the operations layer and will minimize wind entrainment of soil.

37 **4.3.4 Liner System, Foundation [D-6d]**

38 The following sections discuss the foundations beneath the liner systems.

39 **4.3.4.1 Foundation Description [D-6d(1)]**

40 At the IDF, the Hanford formation consists mainly of sand dominated facies with lesser amounts of silt
41 dominated and gravel dominated facies. Where sands are present, these sands are underlain by the

1 Hanford formation. Here, the Hanford formation has been described as poorly sorted pebble to boulder
2 gravel and fine to course grained sand, with lesser amounts of interstitial and interbedded silt and clay.

3 The two geologic units pertinent to the IDF lined landfill are summarized as follows.

4 Recent eolian sand: The sand is light olive gray in color and has a density that is loose at the surface but
5 becomes compact with depth. The sand has a fine to medium grain size and includes little to some
6 nonplastic silt-sized fines. The deposit is homogeneous except for a distinguishable layer of volcanic ash
7 in some locations.

8 Glaciofluvial flood deposit: This deposit has well graded mixtures of sands and gravels with trace to little
9 nonplastic silt-sized particles. The gravel content can vary with depth, and the deposit can become
10 predominantly gravel. This coarse-grained deposit is part of the Cold Creek Bar, which was formed
11 during the Pleistocene Epoch by glacial outburst flooding.

12 **4.3.4.2 Subsurface Exploration Data [D-6d(2)]**

13 Geological site investigations were used to support the detailed design of the landfill. The investigations
14 consisted of a review of historical data, including well logs (Chapter 5.0), exploratory borings, and
15 surface pit samples data. Because the foundation soils are relatively consistent over broad areas, the need
16 for additional borings and geophysical investigations will be determined on a case-by-case basis. If
17 boreholes are drilled, penetration test data will be collected to determine the strength of the foundation
18 materials in situ.

19 **4.3.4.3 Laboratory Testing Data [D-6d(3)]**

20 Laboratory testing will be performed on the surface soil samples and borings, both from the lined landfill
21 site and from potential borrow source locations as follows. Testing will be performed to classify soils,
22 provide input parameters to verify engineering analyses, and for preparing material and construction
23 specifications. The following tests will be performed on the soil samples:

- 24 • Visual classification (ASTM D2487)--to classify soils
- 25 • Natural moisture content (ASTM D2216)--for input to engineering analyses and preparing
26 construction specifications
- 27 • Particle size analysis (ASTM D422 or D1140/C136)--for classification and input to engineering
28 analyses
- 29 • Moisture-density relationships (ASTM D698 or D1557)--for preparing compaction specifications

30 Laboratory testing will be performed according to the most recent versions of ASTM methods or other
31 recognized standards. Additional tests will be performed as needed.

32 **4.3.4.4 Engineering Analyses [D-6d(4)]**

33 The subgrade will be required to support the liner system and overlying materials (waste, fill, and cover)
34 without excessive settlement, compression, or uplift that could damage the liner system. This section
35 describes the design approach used to satisfy these criteria.

36 **4.3.4.4.1 Settlement Potential [D-6d(4)(a)]**

37 The subgrade settlement produced by waste loading essentially will be elastic because of the
38 coarse-grained, noncohesive, and drained nature of the soil. The subgrade will rebound during the
39 excavation phase of construction and will settle as the landfill is filled. An elastic settlement analysis

1 using standard methods was performed and results indicate the magnitude of the total and differential
2 settlement is within performance limits.

3 **4.3.4.4.2 Bearing Capacity [D-6d(4)(b)]**

4 The bearing capacity of the subgrade soil will need to support structures such as leachate collection tanks.
5 The construction specifications typically will require that the upper portion of the subgrade soil and all
6 structural fill be moisture conditioned and compacted to at least 95 percent of the maximum standard
7 Proctor dry density (ASTM D698). Maximum allowable bearing capacities for foundations have been
8 established using standard geotechnical methods. Bearing capacities for the types of soils expected at the
9 IDF typically are greater than the maximum expected loads from the support structures.

10 **4.3.4.4.3 Stability of Lined Landfill Slopes [D-6d(4)(c)]**

11 The lined landfill will be constructed in eolian sand and the underlying coarse-grained Hanford formation.
12 In granular, cohesionless, and drained soils such as these, the stability of the slope will be related
13 primarily to the maximum slope angle. Both veneer and global stability analyses were performed to
14 determine both static and dynamic sideslope stability. Results demonstrate adequate stability for the IDF
15 throughout its design life.

16 **4.3.4.4.4 Potential for Excess Hydrostatic or Gas Pressures [D-6d(4)(d)]**

17 Because the seasonal high-water level is at least 69 meters below the base of the deepest lined landfill, no
18 external hydrostatic pressure will be expected from this source. Because of the coarse-grained nature of
19 the foundation soils, any infiltration of surface water around the perimeter of the lined landfill will be
20 expected to travel primarily downward. Therefore, infiltration should not cause substantial pressure on
21 the exterior of the liner system. Internal hydrostatic pressure from leachate will be negligible because the
22 leachate will be removed from the lined landfill to limit head on the liner.

23 Gas pressure exerted externally on the liner system is expected to be negligible, because no
24 gas-generating material (i.e., organic material) is expected in the foundation soils. If any gas were
25 generated below the liner system, little pressure buildup would occur because of the unsaturated
26 coarse-grained nature of the foundation soils, which would vent the gas to the atmosphere. Internal gas
27 pressure buildup will not be anticipated, because wastes are generally inorganic and have low gas
28 generating potential, and the leachate collection system will be vented to the atmosphere and dissipates
29 any gas.

30 **4.3.4.4.5 Seismic Conditions**

31 Potential hazards from seismic events will include faulting, slope failure, and liquefaction. Disruption of
32 the lined landfill by faulting is not considered a significant risk because (1) no major faults have been
33 identified at the IDF (DOE/RW-0164) and (2) only one central fault at Gable Mountain on the Hanford
34 Site shows evidence of movement within the last 13,000 years. The potential for slope failure is
35 considered low, because granular materials typically have high strengths relative to the maximum
36 sideslope angles expected for the lined landfill. Liquefaction will occur in loose, poorly graded granular
37 materials that are subjected to shaking from seismic events. Saturated soils will be most susceptible
38 because of high dynamic pore pressures that temporarily lower the effective stress. During this process,
39 the soil particles will be rearranged into a more dense configuration, with a resulting decrease in volume.
40 The foundation materials at the IDF is not considered susceptible to liquefaction because the materials are
41 well graded granular soils that are unsaturated and relatively dense.

42 The IDF support building (not sited within the TSD boundary) will be located in Zone 2B as identified in
43 the Uniform Building Code (ICBO 1997).

1 **4.3.4.4.6 Subsidence Potential**

2 In general, subsidence of undisturbed foundation materials would be the result of dissolution, fluid
3 extraction (water or petroleum), or mining. The potential for subsidence will be negligible at the IDF
4 based on the following.

- 5 • The soils underlying the IDF are coarse-grained sands and gravels, in a relatively dense configuration
6 which are not subject to piping that can cause transport of soil and resulting subsidence.
- 7 • The groundwater level is deep, at least 69 meters below the base of the lined landfill, and does not
8 affect bearing soils.
- 9 • The soil and rock types below the IDF are not soluble.
- 10 • No mining or tunneling has been noted. If the groundwater level was lowered substantially and
11 consolidation occurred in the aquifer, local site-specific subsidence would be negligible because of
12 the depth of the groundwater table below the lined landfill.

13 **4.3.4.4.7 Sinkhole Potential**

14 Borings in and around the IDF have not identified any soluble materials in the foundation soils or
15 underlying sediments. Consequently, the potential for any sinkhole development is negligible.

16 **4.3.5 Liner System, Liners [D-6e]**

17 The following sections discuss the individual components of the IDF liner systems.

18 **4.3.5.1 Synthetic Liners [D-6e(1)]**

19 As described in Section 4.3.3, the synthetic liners will act as an impermeable barrier for leachate
20 migration (Figure 4-2). The synthetic liners will consist of high-density polyethylene material that will
21 make the liners resistant to chemical deterioration. Section 4.3.3 describes the synthetic liner system in
22 greater detail.

23 **4.3.5.2 Synthetic Liner Compatibility Data [D-6e(1)(a)]**

24 During detailed design of the lined landfill, the composition of the expected leachate was estimated.
25 Expected leachate composition was based on known waste composition, process information, leachate
26 from other operating lined landfills, and similar sources of data. Leachate constituents were compared to
27 manufacturers' chemical compatibility data for synthetic liner components. In addition, the results of
28 previous chemical compatibility testing and studies were evaluated against leachate composition.
29 Information gained from this evaluation was used to select a liner that will be compatible with the
30 expected leachate.

31 Compatibility testing for leachate tank liner material is planned for construction. An immersion test
32 program is included in the technical specifications for the tank liner (anticipated to be XR-5 material).
33 The immersion testing program will require the construction general contractor to submit tank liner
34 samples to the design engineer for immersion testing as part of the submittal and certification process for
35 the tank. Immersion testing will follow EPA 9090A (and ASTM) test protocols.

36 During landfill operation, the compatibility of waste receipts with the liner will be ensured. The
37 compatibility of the waste constituents with the liner material will be established by laboratory testing if
38 determined to be necessary, based on waste type and concentrations. Such tests will follow EPA Method
39 9090A or other appropriate methods. Test results will be evaluated using statistical methods and accepted
40 criteria (based on past projects and agency acceptance) for liner/leachate compatibility.

1 **4.3.5.3 Synthetic Liner Strength [D-6e(1)(b)]**

2 As discussed in Section 4.3.3.3, the liner system will experience loads from several sources. During the
3 detailed design process for the landfill, the strength of liner system materials was evaluated against these
4 loads. The analysis indicated an adequate factor of safety for liner system materials.

5 Seams in geomembranes will be a critical area. However, with correct installation methods, the seams
6 will be stronger than the surrounding material. Detailed installation and testing requirements will be
7 included in the construction quality assurance plan (Section 4.3.7.3) to ensure that the liner is constructed
8 properly. In addition, methods will be established to demonstrate adequate seam strength is achieved
9 during installation.

10 Seaming requirements for the geotextiles and CDN will not be as stringent. These materials will be
11 overlapped sufficiently to provide complete area coverage, and relatively light seams will be used to hold
12 the panels in position during construction. After the lining system has been completed, seam strength
13 requirements for these materials will be negligible.

14 **4.3.5.4 Synthetic Liner Bedding [D-6e(1)(c)]**

15 The primary geomembrane liner will be in contact with the GCL and geotextile cushion underlying the
16 drainage gravel.

17 The secondary geomembrane liner will be in direct contact with the compacted admix layer. This type of
18 subgrade is typical for flexible geomembrane liners. No problems related to the mechanical integrity of
19 the geomembrane liner will be expected in this application.

20 With respect to the drainage gravel and operations layers, the geomembranes will be protected by
21 overlying geotextile cushion or CDN layers. These geotextiles were designed to provide adequate
22 protection during construction and operation to withstand the loads discussed in Section 4.3.3.3.

23 **4.3.5.5 Soil Liners [D-6e(2)]**

24 The IDF landfill will be lined with a minimum (0.9-meter thick) layer of compacted soil/bentonite
25 mixture (admix) under the secondary geomembrane liner. This layer will have an in-place hydraulic
26 conductivity of less than 1×10^{-7} centimeter per second. The soil component of the admix will be silty
27 fine sand or similar material from areas near the IDF. Approximately 12 percent bentonite by dry weight
28 will be added to the fine soil to achieve sufficiently low hydraulic conductivity; however, the percent
29 might vary. Construction of the liner is discussed in Section 4.3.7.

30 **4.3.5.5.1 Material Testing Data [D-6e(2)(a)]**

31 Laboratory testing will be performed on soil liner materials to confirm input parameters for engineering
32 analyses and for refining material and construction specifications.

33 Before constructing the lined landfill, a full-scale test fill of the admix material will be conducted. The
34 primary purpose of the test fill will be to verify that the specified soil density, moisture content, and
35 hydraulic conductivity values will be achieved consistently using proposed compaction equipment and
36 procedures. In-place density will be measured using both the nuclear gauge (ASTM D2922) and sand
37 cone (ASTM D1556) methods. In-place hydraulic conductivity will be determined from a two stage
38 infiltration from a borehole (ASTM D6391). Admix hydraulic conductivity will be estimated from
39 thin-wall tube samples (ASTM D1587) obtained from the test fill and tested in the laboratory (ASTM
40 D5084). Details of the test fill are presented in the Construction Quality Assurance Plan (Appendix 4B).
41 During construction, field density (e.g., ASTM D2922, D2167, and/or D1556) and moisture content
42 (ASTM D2216) will be measured periodically. Thin-wall tube samples (ASTM D1587) will be taken at

1 regular intervals and will be tested for hydraulic conductivity (ASTM D5084). Additional details of field
2 testing during construction will be presented in the Construction Quality Assurance Plan.

3 Dispersion and piping in the admix are not considered likely because the hydraulic conductivity, and thus
4 the flow velocity, will be very low, making it difficult to move the soil particles or otherwise disrupt the
5 soil fabric. In addition, the admix will be well graded, so the component particles will tend to hold each
6 other in place. Therefore, testing for these characteristics will not be necessary.

7 **4.3.5.5.2 Soil Liner Compatibility Data [D-6e(2)(b)]**

8 As discussed in Section 4.3.5.2, expected leachate composition was determined as part of detailed landfill
9 design. The results of previous chemical compatibility testing and studies were evaluated against leachate
10 composition to determine the effect of leachate on soil liner composition or hydraulic conductivity. The
11 tests followed the procedures of ASTM D5084 (flexible wall parameter) and considered the effects of
12 radiation on the soil liner materials.

13 **4.3.5.5.3 Soil Liner Thickness [D-6e(2)(c)]**

14 The IDF has been designed and will be operated to minimize the leachate head over the liner systems.
15 Design of the primary liner system has included an additional clay layer (the primary GCL layer, which
16 was previously described in Section 4.3.3.1) underlying the primary HDPE geomembrane to further
17 minimize liner leakage from the primary liner. Note that only a single geomembrane is required under
18 WAC 173-303 for the primary liner.

19 Calculations were performed to evaluate the effectiveness of the primary soil liner as a barrier to leachate.
20 Leakage analyses were performed for the primary liner system using EPA's Hydrologic Evaluation of
21 Landfill Performance (HELP) Model (Schroeder et al. 1997). Estimated leakage rates were compared to
22 the Action Leakage Rate (ALR, which is defined in WAC 173-303-665[8] as "the maximum design flow
23 rate that the leak detection system ... can remove without the fluid head on the bottom liner exceeding
24 1 foot"), and were determined to be much lower than the ALR. This demonstrates the benefit of the GCL
25 included in the primary bottom lining system, which provides a composite lining system and minimizes
26 actual leakage through the bottom primary lining system.

27 Overall, the IDF is designed to actively convey and collect leachate from the liner areas of the facility to
28 minimize leachate buildup over the liners. Leachate is conveyed to the LCRS and LDS sumps for active
29 removal from the facility. In addition, the LCRS sump area has been designed with a 6-inch-deep sump
30 trough where the LCRS pumps are positioned to minimize the area of the sump that has a permanent
31 liquid level (below the pump intake/shutoff elevation). Both the LCRS and LDS sump pumps will be
32 operated throughout the active life of the facility and into the post-closure time period until leachate
33 generation has essentially ceased. By actively removing leachate from the IDF, head buildup is
34 minimized, which in turn minimizes leakage through both the primary and secondary liner systems.

35 **4.3.5.5.4 Soil Liner Strength [D-6e(2)(d)]**

36 The expected loads on the liner system are discussed in Section 4.3.3.3. Significant stresses in the soil
37 liner that were considered include (1) stresses from the weight of the liner system, (2) stresses on the
38 interface with the overlying materials, and (3) stresses during construction.

39 Stresses will be present on the sideslopes from the weight of the operations layer and soil liner itself.
40 Using material properties determined from laboratory testing, the stability of the soil liner were evaluated
41 under both static and dynamic loading conditions. Standard methods of slope stability analysis were
42 used. Interface strengths were found to provide adequate veneer stability for the liner system. Interface
43 strength is the shear strength that occurs between layers of liner materials at their interface boundary, as
44 established by ASTM test methods.

1 The primary concern during construction will be bearing failure caused by the weight of overlying soil
2 components of the liner system (e.g., drainage gravel on the floor) and the construction equipment used to
3 spread these materials. Strength parameters developed from laboratory testing and standard analytical
4 methods were again used to determine that adequate stability and bearing capacity exist for the IDF liner
5 system.

6 **4.3.5.5 Engineering Report [D-6e(2)(e)]**

7 An engineering report was prepared for the lined landfill as part of the definitive design document
8 package. The report describes the design of the liner system and includes supporting calculations. The
9 critical systems IDF Design Report is provided in Appendix 4A. The final IDF design report was
10 prepared under the supervision of a professional engineer registered in Washington State.

11 **4.3.6 Liner System, Leachate Collection and Removal System [D-6f]**

12 The purpose of the leachate collection and removal system will be to provide sufficient hydraulic
13 conductivity and storage volume to collect, retain, and dispose of, in a timely manner, fluids falling on or
14 moving through the waste. The primary leachate collection and removal system will provide the
15 preferential path along which the leachate will flow into the primary sump. The secondary leachate
16 collection and removal system (also called the leak detection system) will be located between the primary
17 and secondary geomembranes. The secondary leachate collection and removal system will provide the
18 preferential path along which any fluids leaking through the primary liner system flow to the secondary
19 sump.

20 The collected leachate will be pumped to a leachate collection tank, screened and/or sampled, and
21 transferred to a permitted treatment and disposal unit.

22 **4.3.6.1 System Operation and Design [D-6f(1)]**

23 The lined landfill will be operated in a way that ensures the bottom liner is maintained as dry as possible,
24 and the head on the top liner does not exceed 30.5 centimeters measured above the flat 50-foot by 50-foot
25 LCRS sump HDPE liner. In extreme conditions (i.e., in excess of a 25-year storm event), the head on the
26 top liner could exceed 30.5 centimeters for short durations. The operating methodology, described in the
27 following paragraphs, will ensure that liquids on the bottom liner are removed continuously before liquids
28 could accumulate and exceed 30.5 centimeters for the design storm event.

29 Both leachate collection systems either will be operated manually or automatically. When operated
30 automatically, liquid level sensors will cycle the pumps on and off, in response to rising and falling
31 leachate levels. The leakage rate through the top liner will be calculated to demonstrate that the leakage
32 rate is less than the 'action leakage rate'. Data to support the leakage rate calculations will be obtained
33 either from the flow totalizer in the secondary leachate collection pump discharge line or from the liquid
34 level gauges. Collected leachate from the secondary leachate collection system will be pumped to the
35 leachate collection tank.

36 The design of the primary and secondary leachate collection systems is described in Section 4.3.3.1.
37 System geometry was completed and material specifications were developed during the detailed design
38 process. The leachate collection and removal system design will comply with WAC 173-303
39 requirements and applicable guidance.

40 Each sump will have a thick layer of gravel designed to provide high hydraulic conductivity and storage
41 capacity. Leachate will be removed from the sumps by a pump installed in sideslope riser pipes. Pressure
42 transducers will be used to monitor leachate level in the sumps and will provide appropriate signals to the
43 pump control system. All pumps and transducers will be removable for maintenance, calibration, and
44 related activities.

1 **4.3.6.1.1 Primary System**

2 The base of the leachate collection and removal system will be defined by the primary geomembrane. On
3 the floor of the lined landfill, the primary geomembrane will be overlain by geotextile cushion, and the
4 granular drainage layer. The granular drainage layer will drain to the primary sump and a perforated pipe
5 will be located along the centerline of the cell to increase flow capacity to the primary sump. Geotextile
6 layers at the top of the leachate collection and removal system will prevent migration of fine soil particles
7 into the gravel or geonet, thus prevent clogging. On the sideslopes, a CDN layer will be used over the
8 geomembrane. The CDN will include bonded geotextiles on both sides of a geonet that increase the
9 interface shear strength. Because of construction difficulties in placing a 30.5-cm thick gravel layer on
10 3:1 sideslopes, no drainage gravel will be placed on the sideslopes.

11 The leachate collection and removal system will be covered by the operations layer. The layer will be a
12 minimum 0.9-meter thick, and will provide protection for the underlying liner and drainage materials.
13 The operations layer will cover both the landfill floor and the sideslopes.

14 The leachate collection and removal system will be designed to accommodate the 25-year, 24-hour storm,
15 as required by WAC regulations. However, the EPA recognizes the need to temporarily store leachate
16 from such rare events (EPA 1985). Should a storm event that exceeds the 25-year, 24-hour storm event
17 occur, the leachate collection and removal system sump was designed to temporarily store leachate at a
18 depth greater than 30.5 centimeters, as opposed to the alternative of constructing an excessively large
19 leachate collection tank.

20 The leachate collection and removal system sump will be equipped with two sump pumps. One pump
21 will be a high capacity pump capable of rapid removal of large volumes of leachate, will be suitable for
22 the transfer of batch quantities of leachate, and will handle the larger volumes of leachate anticipated
23 from the 25-year, 24-hour storm event. The other pump will be a low-capacity submersible pump located
24 in the base of the sump. The sump pumps will be located in a sump trough. The sump trough was
25 designed to contain the leachate below the intake of these pumps, within the smallest possible area, to
26 minimize the residual leachate volume after each pumping cycle. The pumps will be fabricated from
27 stainless steel or other corrosion resistant material.

28 **4.3.6.1.2 Leak Detection System**

29 The base of the LDS will be formed by the secondary geomembrane. The leak detection system will be
30 similar to the LCRS, except that the perforated collection pipe is not included. The perforated pipe will
31 not be needed because high flow capacity will not be required for the low leachate volumes.

32 The LDS will drain to the LDS sump, which will be located immediately below the LCRS sump.
33 Because of the low volumes, the LDS will be equipped with only one low-capacity submersible pump to
34 meet WAC 173-303-665(8)(a).

35 **4.3.6.1.3 Response Action Plan**

36 In compliance with regulatory requirements, a response action plan (Appendix 4C) was prepared for the
37 lined landfill. In accordance with EPA guidance, the action leakage rate was calculated as "the maximum
38 design flow rate that the leak detection system can remove without the fluid head on the bottom liner
39 exceeding 30.5 centimeters" (EPA 1992). If the action leakage rate were exceeded, DOE will do the
40 following:

- 41 • Notify the appropriate regulatory authority in writing of the exceedence within 7 days of the
42 determination

- 1 • Submit a preliminary written assessment to the appropriate regulatory authority within 14 days of the
2 determination, on the amount of liquids, likely sources of liquids, possible location, size, cause of any
3 leaks, and short-term actions taken and planned
- 4 • Determine to the extent practicable the location, size, and cause of any leak
- 5 • Determine whether waste receipt should cease or be curtailed, whether any waste should be removed
6 from the unit for inspection, repairs, or controls, and whether the unit should be closed
- 7 • Determine any other short-term and/or long-term actions to be taken to mitigate or stop any leaks
- 8 • Within 30 days after the notification that the action leakage rate has been exceeded, submit to the
9 appropriate regulatory authority the results of the analyses specified in the following paragraphs, the
10 results of actions taken, and actions planned. Monthly thereafter, as long as the flow rate in the leak
11 detection system exceeds the action leakage rate, DOE will submit to the appropriate regulatory
12 authority, a report summarizing the results of any remedial actions taken and actions planned.

13 The leachate will be analyzed for RCRA constituents as appropriate. A procedure will be in place to
14 address details of analysis (i.e., analyses, constituents, test methods, etc.). If the analytical results on
15 leakage fluids indicate that these constituents are present, and if the constituents can be traced to a
16 particular type of waste placed in a known area of the lined landfill, it might be possible to estimate the
17 location of the leak. In addition, waste packages might not undergo enough deterioration during the
18 active life of the landfill to permit escape of the contents; it is possible that the leachate might be clean or
19 the composition too general to show a specific source location.

20 If the source location cannot be identified, large-scale removal of the waste and operations layer to find
21 and repair the leaking area of the liner would be one option for remediation. However, this risks
22 damaging the liner. In addition, waste would have to be handled, stored, and replaced in the landfill.
23 Backfill would need to be removed from around any waste packages to accomplish this. If the waste
24 packages were damaged during this process, the risk of accidental release might be high. For these
25 reasons, large-scale removal of waste and liner system materials will not be a desirable option and will
26 not be implemented except as a last resort.

27 The preferred alternative will depend on factors such as the amount of waste already in the landfill, the
28 rate of waste receipt, the chemistry of the leachate (i.e., is it clean?), the availability of other disposal
29 units, and similar considerations. Therefore, no single approach will be selected at this time. If
30 necessary, an interim solution could be implemented while the evaluation and permanent remediation
31 were performed. Examples of potential approaches include the following.

- 32 • The surface of the waste could be graded to direct run-off into a shallow pond. The surface would be
33 covered with the low-hydraulic conductivity layer (geomembrane). Precipitation would be pumped
34 or evaporated from the pond and would not infiltrate the waste already in the lined landfill. Waste
35 would be placed only during periods of dry weather, and stored at other onsite TSD units at other
36 times. This type of approach also could be used to reduce leakage immediately after the action
37 leakage rate was exceeded, while other remediation options were evaluated.
- 38 • Partial construction of the final closure cover could begin earlier than planned. This would reduce
39 infiltration into the lined landfill, and possibly reduce the leakage rate if the cover were constructed
40 over the failed area.
- 41 • A layer of low-hydraulic conductivity soil could be placed over the existing waste, perhaps in
42 conjunction with a geomembrane, to create a second 'primary' liner higher in the lined landfill. This
43 new liner would intercept precipitation and allow its removal.

- 1 • A rigid-frame or air-supported structure could be constructed over the landfill to ensure that no
2 infiltration occurs. Although costly, this approach could be less expensive than constructing a new
3 landfill.

4 In general, the selected remediation efforts will be progressive. Those remediation methods that are
5 judged to be the least difficult and the most cost effective will be used first. If these efforts are not
6 effective, more difficult or expensive options would be used.

7 **4.3.6.2 Equivalent Capacity [D-6f(2)]**

8 The CDN drainage layers used will be available commercially and will have equivalent flow capacity to a
9 30.5-centimeters layer of granular drainage material with a hydraulic conductivity of 1×10^{-2} centimeter
10 per second.

11 **4.3.6.3 Grading and Drainage [D-6f(3)]**

12 In accordance with EPA guidance, all areas of the lined landfill floor (except the sump bottoms) will be
13 graded at a slope of at least 2 percent towards the centerline of each cell. The centerline of each cell will
14 have a 1 percent slope lengthwise towards the sump, to facilitate drainage and avoid ponding on the
15 liners. Grading tolerances have been established to ensure proper slope is maintained.

16 **4.3.6.4 Maximum Leachate Head [D-6f(4)]**

17 The maximum head on the primary liner will be less than 30.5 centimeters, except for rare storm events as
18 discussed in Section 4.3.6.1 and the LCRS sump trough. The sump was sized and designed to provide
19 adequate surge storage to prevent leachate build up on the primary liner.

20 **4.3.6.5 System Compatibility [D-6f(5)]**

21 The primary and secondary leachate collection and removal systems will be composed of inert geologic
22 materials (sand and gravel), high-density polyethylene, and other geosynthetic materials such as
23 polypropylene. As described in Section 4.3.5.2, the geosynthetics were evaluated for compatibility with
24 the expected leachate. To ensure that the geosynthetics used in the lined landfill are similar chemically to
25 those evaluated, manufacturers will be required to submit quality control certificates and other
26 manufacturing information on all materials.

27 Before a new waste constituent, not previously analyzed (based on a dangerous waste number), is allowed
28 in the lined landfill, the waste constituent will be evaluated for compatibility with the liner (e.g., identified
29 in 9090A test results or other appropriate testing methods, etc.). Other materials could contact the
30 leachate, for example:

- 31 • HDPE and Polyvinyl chloride (PVC) piping will be used
32 • Polyvinyl chloride and other plastics in miscellaneous uses
33 • Leachate tank will use a chemically resistant flexible geomembrane liner system.

34 Compatibility of these materials with the expected leachate was considered in the landfill liner system
35 design. Compatibility of these materials will be of lesser concern, because items that consist of these
36 materials will be located entirely within the containment area. Failure of these items would not result in a
37 dangerous waste release, and the materials would be replaced or repaired.

1 **4.3.6.6 System Strength [D-6f(6)]**

2 Stability of drainage layer, strength of piping, and prevention of clogging are discussed in the following
3 sections.

4 **4.3.6.6.1 Stability of Drainage Layers [D-6f(6)(a)]**

5 As described in Sections 4.3.3.3 and 4.3.5.3, the stability of the liners and leachate collection and removal
6 systems on the sideslopes was evaluated as part of detailed design (Appendix 4A). To provide
7 sufficiently high shear strengths at the interfaces between geosynthetic components, textured
8 geomembranes and thermally bonded CDNs are used.

9 Bearing capacity of the drainage and sump gravels is expected to be adequate, based on typical strength
10 values for granular materials.

11 The transmissivity of the drainage layers under the combined load of the waste and cover was addressed
12 in the design and will be adequate to support leachate removal.

13 **4.3.6.6.2 Strength of Piping [D-6f(6)(b)]**

14 The drain pipes in the primary drainage and sump gravel and sideslope riser pipes will be high-density
15 polyethylene pipe. During detailed design, the required wall thickness of the pipe was determined
16 according to the manufacturer's recommendations and standard analytical methods used by the piping
17 industry (Appendix 4A). In these analyses, the ultimate load (derived from the estimated weight of the
18 waste and cover) was used, the allowable deflections were limited to 5 percent, and conservative values
19 for soil modulus and lateral confinement were assumed.

20 **4.3.6.7 Prevention of Clogging [D-6f(7)]**

21 The geotextiles that separate the drainage layers from adjacent soil layers was selected based on the
22 ability of the geotextiles to retain the soil and to prevent the soil from entering the leachate collection and
23 removal systems. In addition, the amount of fine material in the drainage and sump gravels will be
24 limited by specification to less than a few percent, and will not be expected to cause clogging problems
25 (Appendix 4A). Because the waste disposed in the lined landfill will be required to satisfy LDR
26 (RCW 70.105.050(2), WAC 173-303-140, and 40 CFR 268), the amount of organic material will be
27 minimal, and consequently biologic clogging will not be a problem.

28 **4.3.7 Liner System, Construction and Maintenance [D-6g]**

29 Details relating to the liner system construction and maintenance are discussed in the following sections.

30 **4.3.7.1 Material Specifications [D-6g(1)]**

31 Material specifications are provided in the following sections for each of the materials used in the liner
32 system.

33 **4.3.7.1.1 Synthetic Liners [D-6g(1)(a)]**

34 As described in Section 4.3.3.1, both the primary and secondary geomembrane liners will consist of
35 high-density polyethylene. As described in Section 4.3.3.1.4, the primary barrier also contains a
36 geosynthetic clay liner placed on the floor area only. Detailed specifications were prepared for the lined
37 landfill as part of the design process.

1 **4.3.7.1.2 Soil Liners [D-6g(1)(b)]**

2 As described in Section 4.3.3.1, the soil liner will consist of imported bentonite (expansive clay) blended
3 with fine soil deposits on or next to the IDF. The fine soil will be free of roots, woody vegetation, rocks
4 greater than 2.54 centimeter in diameter, and other deleterious material. The bentonite content will
5 depend on the characteristics of the fine soil. Mixing will be performed under carefully controlled
6 conditions in a pugmill or other approved alternatives. The admix will be placed and compacted to
7 achieve an in-place hydraulic conductivity of 1×10^{-7} centimeter per second or less. The final surface of
8 the soil liner will be rolled smooth before placing the overlying geomembrane. Additional specifications
9 were prepared for the lined landfill as part of the design process.

10 **4.3.7.1.3 Leachate Collection and Removal System [D-6g(1)(c)]**

11 Drainage and sump gravel will consist of hard, durable, rounded to subrounded material. The gravel will
12 be washed and the amount of fine material (i.e., passing the number 200 sieve) will be limited to a few
13 percent. The hydraulic conductivity of the gravel will be 1×10^{-2} centimeter per second or greater.
14 Additional specifications were prepared as part of the design process.

15 For geotextiles and geonets, the composition, thickness, transmissivity, unit weight, apparent opening
16 size, strength, and other properties were determined during detailed design based on results of engineering
17 analyses, experience, and industry standard approaches.

18 **4.3.7.2 Construction Specifications [D-6g(2)]**

19 Construction requirements for major components of the lined landfill are summarized in the following
20 sections.

21 **4.3.7.2.1 Liner System Foundation [D-6g(2)(a)]**

22 The excavated subgrade surfaces will be moisture conditioned and compacted as required to achieve the
23 specified compaction before placing the admix layer.

24 **4.3.7.2.2 Soil Liners [D-6g(2)(b)]**

25 The soil and bentonite will be blended thoroughly and moisture conditioned so that the admix will be
26 uniform and homogeneous throughout. The admix layer will be placed in loose lifts and compacted so
27 that the compacted lift meets the requirements of the Construction Quality Assurance Plan. Each new lift
28 of admix will be kneaded into the previously placed lift. The methods for admix preparation, type of
29 compaction equipment, number of passes, and other details of the placement process will be determined
30 by constructing a test fill section before placing admix in the lined landfill.

31 **4.3.7.2.3 Synthetic Liners [D-6g(2)(c)]**

32 To protect the overlying geomembranes, the admix surface will be smooth and free of deleterious
33 material. In all cases, the high-density polyethylene liner will be deployed with the length of the roll
34 parallel to the slope. Adjacent panels will be overlapped and thermally seamed using fusion or extrusion
35 methods. Seams will be inspected continuously using air pressure tests. A vacuum box will be used in
36 areas where air pressure tests cannot be used (e.g., extrusion weld areas). Destructive seam tests (ASTM
37 D4437) (peel and adhesion) will be performed on samples taken at regular intervals. Placing the
38 overlying geosynthetic layers when practicable will protect the geomembranes.

39 **4.3.7.2.4 Leachate Collection and Removal Systems [D-6g(2)(d)]**

40 Drainage and sump gravel will be placed and spread carefully over the underlying geosynthetics using
41 suitable equipment to prevent damage. Hauling and placing equipment will operate on a minimum

1 thickness of soil above any geosynthetic layer to avoid damage. Geosynthetic layers in the leachate
2 collection and removal system will be deployed, overlapped, and joined (e.g., tying for geonets, sewing
3 for geotextiles) according to standard industry practice and the manufacturers' recommendations.
4 Drainage and riser pipes will be installed in the landfill. Pipes will be bedded carefully and the landfill
5 will be backfilled to provide adequate lateral support. Pumps and other mechanical components will be
6 installed according to manufacturers' recommendations.

7 **4.3.7.3 Construction Quality Control Program [D-6g(3)]**

8 A construction quality assurance plan (Appendix 4B) will be used during lined landfill construction and
9 establishes in detail the following in accordance with WAC 173-303-335:

10 Program must include observations, test, and measurements to ensure

- 11 • proper construction of all components of the liners, leachate collection and removal system,
- 12 • conformity of all materials used in the design.

13 **4.3.7.4 Maintenance Procedures for Leachate Collection and Removal Systems [D-6g(4)]**

14 The accessible components of the leachate collection and removal system will be maintained according to
15 preventive maintenance methods. These methods will require periodic testing to prove that the
16 equipment, controls, and instrumentation are functional and are calibrated properly. Testing intervals will
17 be derived from applicable regulations and manufacturer's recommendations. All pumps and motors will
18 be started or bumped monthly or at intervals suggested by the manufacturer; first, to demonstrate that the
19 pumps and motors are functional, and second, to move the bearing(s) so that the bearing surfaces do not
20 seize or become distorted. Instruments will be calibrated annually or at intervals suggested by the
21 manufacturer. When applicable, the preventive maintenance methods will include calibration
22 instructions. The following instruments will require annual calibration:

- 23 • LCRS sump level indicator
- 24 • LDS sump level indicator

25 Other instrumentation inside the leachate handling and storage facilities will also require routine
26 maintenance.

27 **4.3.7.5 Liner Repairs During Operations [D-6g(5)]**

28 Because of the 0.9-meter-thick operations layer, damage to the liner system is not expected. If damage
29 did occur, the operations layer could be removed laterally as far as required. Underlying geosynthetic and
30 gravel layers will be removed until an undamaged layer is encountered. The damaged layers will be
31 repaired and replaced from the lowest layer upwards using similar methods to those employed during
32 construction. Most repairs to the geomembranes will be performed using a patch, which will be placed,
33 welded, and tested by construction quality assurance personnel.

34 **4.3.8 Run-On and Run-Off Control Systems [D-6h]**

35 Because of the sandy soils, small drainage area, and arid climate at the IDF, stormwater run-on and
36 run-off will not be expected to require major engineered structures. Interceptor and drainage ditches will
37 be adequate for run-on and run-off control. The 25-year, 24-hour precipitation event was the design
38 storm used to size the lined landfill systems. Beyond this, surface water evaluation is highly site-specific,
39 and appropriate analyses were performed as part of detailed design for the lined landfill.

1 **4.3.8.1 Run-On Control System [D-6h(l)]**

2 Run-on will be controlled by drainage ditches or berms around the perimeter of the lined landfill. Any
3 overland flow approaching the landfill will be intercepted by the ditches or berms and will be conveyed to
4 existing drainage systems or suitable discharge points. All the drainage ditches or berms were designed
5 to handle the peak 25-year flow from the potential drainage area. By using low channel slopes, design
6 flow velocities in the ditches will be maintained below established limits for sand channels.

7 Between the landfill crest and the perimeter road, the area will be graded to provide drainage toward the
8 perimeter road. The perimeter road will be sloped outward, at a grade of approximately 2 percent, to
9 provide drainage away from the landfill. On the outside of the perimeter road drainage ditches will be
10 excavated to provide drainage away from the landfill.

11 **4.3.8.1.1 Design and Performance [D-6h(1)(a)]**

12 Design and performance details were determined for the landfill as part of the detailed design process.

13 **4.3.8.1.2 Calculation of Peak Flow [D-6h(1)(b)]**

14 Computation of design discharge for the drainage ditches or berms was performed using standard
15 analytical methods, such as the Rational Method or the computer program HEC-1 (USACE 1981). The
16 25-year, 24-hour precipitation depth is 4.0 centimeters, based on precipitation data recorded from 1947 to
17 1969 (PNL-4622). The tributary area for each section of ditch or berm was based on local topography.

18 **4.3.8.2 Run-Off Control System [D-6h(2)(a and b) and (3)]**

19 There will be no run-off from the lined landfill because the landfill will be constructed below grade. Any
20 precipitation falling on the landfill will be removed by either evapotranspiration or the leachate collection
21 and removal systems. Therefore, a run-off control system will not be needed.

22 **4.3.8.3 Construction [D-6h(4)]**

23 The drainage ditches or berms around the lined landfill will be constructed with conventional
24 earthmoving equipment such as graders and small dozers.

25 **4.3.8.4 Maintenance [D-6h(5)]**

26 The drainage ditches or berms will require periodic maintenance to ensure proper performance. The most
27 frequent maintenance activity, beyond periodic inspection, will be cleaning the ditches or berms to
28 remove obstructions caused by windblown soil and vegetation (e.g., tumbleweeds). After rare storm
29 events, regrading of the ditch bottom or repair of the berm might be required to repair erosion damage.
30 This is expected to occur infrequently; however, inspections will be conducted after 25-year storm events
31 or at least annually.

32 **4.3.9 Control of Wind Dispersal [D-6i]**

33 The IDF will use varied methods to prevent wind dispersal of mixed waste and backfill materials,
34 depending on the waste form. Methods to prevent wind dispersal include containerizing, stabilizing,
35 grouting, spray fixitants, and backfill. In other instances, the operating contractor implements a wind
36 speed restriction during handling, and immediately backfills the waste to prevent wind dispersal.

37 **4.3.10 Liquids in Landfills [D-6j]**

38 Free liquids will not be accepted except as allowed by Chapter 3.0, Section 1.2. Waste received at the
39 IDF must comply with waste acceptance requirements.

1 **4.3.11 Containerized Waste [D-6k]**

- 2 Containerized waste received in the IDF lined landfill will be limited to a maximum of 10 percent void
3 space. Several inert materials (diatomaceous earth, sand, lava rock) will be used as acceptable void space
4 fillers for waste that does not fill the container.

OFFICIAL USE ONLY


1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19

This section has been identified as
“Official Use Only” (OUO)
and is available to view by appointment at the
Nuclear Waste Program Resource Center
3100 Port of Benton Blvd.
Richland, Washington

Please contact Valarie Peery at
(509) 372-7920
for a viewing appointment.

1

Figure 4.1. Example of a Typical Liner.



1
2
3
4
5

This page intentionally left blank.