

1
2
3
4

**PART V, CLOSURE UNIT GROUP 21 CONDITIONS
216-B-63 TRENCH**

DRAFT

1
2
3

This page intentionally left blank.

DRAFT

**PART V, CLOSURE GROUP 21 CONDITIONS
216-B-63 TRENCH**

UNIT DESCRIPTION

The 216-B-63 Trench is a non-operational, open, man-made earthen percolation unit that is regulated as an unlined (non-compliant) dangerous waste surface impoundment. The 216-B-63 Trench was used to receive emergency cooling water and chemical sewer waste from B Plant (221-B Canyon Building). The 216-B-63 Trench has not received liquid waste since February 1992. The nature and approximate quantity of dangerous waste managed by the 216-B-63 Trench is known and identified on the Part A Form.

Because the 216-B-63 Trench has received a known final volume of dangerous waste, and the unit will not receive any additional non-dangerous waste, this unit will close according to the requirements and schedules in the approved closure plan in this chapter of the Permit.

The closure of the 216-B-63 Trench will be coordinated with final CERCLA remedial actions in the 200 Area. Specifically, soil cleanup will be coordinated with the 200-EA-1 Operable Unit and groundwater cleanup will be coordinated with the 200-BP-5 Operable Unit in the manner outlined in the *Hanford Federal Facility Agreement and Consent Order* (HFFACO) Action Plan, Section 5.5, and in accordance with schedules in HFFACO Milestones M-037-02 and M-037-10.

LIST OF ADDENDA

| | |
|------------|---|
| Addendum A | Part A Form |
| Addendum B | Sampling and Analysis Plan – Reserved |
| Addendum C | Process Information – Reserved |
| Addendum D | Groundwater Monitoring Plan |
| Addendum E | Security Requirements - Reserved |
| Addendum F | Preparedness and Prevention Plan – Reserved |
| Addendum G | Personnel Training |
| Addendum H | Closure Plan and Post-Closure Plan – Reserved |
| Addendum I | Inspection Schedule |
| Addendum J | Contingency Plan – Reserved |

DEFINITIONS

Reserved

ACRONYMS

Reserved

V.21.A COMPLIANCE WITH PERMIT CONDITIONS

The Permittees will comply with all permit conditions in this Chapter and its addenda with respect to the applicable requirements in Part I and Part II of the Hanford Facility Dangerous Waste Permit.

V.21.B CLOSURE

V.21.B.1 The Permittees will submit a closure plan and post-closure plan in accordance with the schedule specified in HFFACO Milestone M-037-02, which are incorporated by reference herein under the terms of Permit Condition I.A.4 and in compliance with Permit Condition I.C.3. (Attachment 1) As part of the closure plan, the Permittees will address contingent closure and contingent post-closure requirements. The contingent

- 1 closure and post-closure section will include time frames of when detailed plans of a
2 landfill cover would be submitted for Ecology review and approval and when the
3 construction of the landfill cover would begin once the Permittees have determined the
4 unit cannot meet clean closure standards.
- 5 **V.21.B.2** The Permittees will submit site specific biological and cultural resources reviews 90 days
6 before the beginning of the closure process. [[WAC 173-303-815\(2\)\(b\)\(i\)](#)].
- 7 **V.21.B.3** The closure plan required by V.21.B.1 will include a schedule for closure that will
8 achieve the HFFACO milestone date in Milestone M-037-10, as incorporated above
9 (Attachment 1). This unit will also close under a compliance schedule per [WAC 173-](#)
10 [303-815\(3\)\(b\)](#).
- 11 **V.21.B.4** The closure plan submitted pursuant to V.21.B.1 will specify dangerous constituents and
12 corresponding closure performance standards to meet the requirements of [WAC 173-303-](#)
13 [610\(2\)\(b\)\(i\)](#) for soils affected by the operations associated with this unit.
- 14 **V.21.B.5** Closure performance standards for soils will satisfy the most stringent (lowest) cleanup
15 level or standard of [WAC 173-340](#), Model Toxics Control Act (MTCA) Cleanup
16 Regulation. The numeric cleanup levels for soils will be calculated according to the
17 MTCA cleanup methods described in [WAC 173-340-700](#) through [WAC 173-340-760](#).
18 Selection of an appropriate MCTA cleanup method will be dependent on the specific
19 cleanup actions required for this site.
- 20 **V.21.B.6** Once the closure plan is incorporated into Addendum H through the permit modification
21 process the Permittees will close the 216-B-63 Trench according to the requirements in
22 Addendum H. [[WAC 173-303-610\(3\)\(a\)](#)]
- 23 **V.21.B.7** The closure plan and sampling and analysis plan will meet the applicable closure and
24 post-closure requirements of [WAC 173-303-610](#) and [WAC 173-303-650\(6\)](#) pursuant to
25 the requirements of this Chapter.
- 26 **V.21.B.8** In conjunction with the revised closure plan, the Permittees will submit a revised
27 sampling and analysis plan in accordance with Permit condition II.D.3 and the schedule
28 specified in HFFACO Milestone M-037-02, which are incorporated by reference herein
29 under the terms of Permit Condition I.A.4.
- 30 **V.21.B.9** The revised sampling and analysis plan (noted in V.21.B.8) will include, but not be
31 limited to:
- 32 **V.21.B.9.a** Process for identifying contaminants
- 33 **V.21.B.9.b** Quality assurance/quality control project plan
- 34 **V.21.B.9.c** Methods for representative soil sampling
- 35 **V.21.B.9.d** Analysis parameters
- 36 **V.21.B.9.e** Analytical documentation
- 37 **V.21.B.10** The Permittees will conduct all sampling and analysis of environmental media pursuant
38 to the requirements of the sampling and analysis plan.
- 39 **V.21.C** **POST-CLOSURE CARE AND MAINTENANCE**
- 40 Upon certification of unit closure the Permittees will comply with the post-closure plan in
41 Addendum H.
- 42 **V.21.D** **GENERAL WASTE MANAGEMENT REQUIREMENTS**

- 1 **V.21.D.1** All waste analysis required by this chapter will be conducted according to the approved
2 sampling and analysis plan.
- 3 **V.21.D.2** Changes to the analytical methods used in this permit will require prior Ecology approval
4 according to [WAC 173-303-830](#), Permit Changes.
- 5 **V.21.E** **GROUNDWATER MONITORING REQUIREMENTS FOR REGULATED UNITS**
- 6 **V.21.E.1** The Permittees will implement the interim status groundwater monitoring plan until a
7 final status groundwater monitoring plan, as required by Permit Condition V.21.E.2, is
8 incorporated into the Permit. The interim status groundwater monitoring plan for the
9 216-B-63 Trench is contained in Addendum D to this Chapter. (*DOE/RL-2008-60*
10 *Revision 0, Interim Status Groundwater Monitoring Plan for the 216-B-63 Trench*)
- 11 **V.21.E.2** The Permittees will submit a final status groundwater monitoring plan in conjunction
12 with a final closure plan as specified in Permit Condition V.21.B.1. The Permittees may
13 choose to submit a final groundwater monitoring plan that complies with the alternative
14 groundwater monitoring protection requirement provision in [WAC 173-303-645](#)(1)(e), as
15 specified in Permit Condition II.F.2.
- 16 **V.21.F** **RECORDKEEPING AND REPORTING**
- 17 The Permittees will place documentation of all work conducted pursuant to this Chapter
18 including results of all monitoring, testing, or analytical work and associated quality
19 assurance and quality control data in the Hanford Facility Operating Record, as required
20 by Permit Condition II.I.2. [[WAC 173-303-380](#)]
- 21 **V.21.G** **SECURITY**
- 22 The Permittees will post signs at access points to the 216-B-63 Trench stating the
23 following (or an equivalent legend): Danger – Unauthorized Personnel Keep Out. These
24 signs will be written in English, legible from a distance of 7.6 meters (25 feet), and
25 visible from all angles of approach. [[WAC 173-303-310](#)(2)(a)]
- 26 **V.21.H** **PREPAREDNESS AND PREVENTION**
- 27 Reserved
- 28 **V.21.I** **CONTINGENCY PLAN**
- 29 Reserved
- 30 **V.21.J** **INSPECTIONS**
- 31 **V.21.J.1** The Permittees will follow the inspection schedule in Addendum I and Permit Condition
32 II.X until closure of the unit.
- 33 **V.21.J.2** In the event of any potential threats to human health or the environment, the Permittees
34 will increase inspections to quarterly until the threats are removed.
- 35 **V.21.K** **TRAINING PLAN**
- 36 The Permittees will comply with the training requirements as described in Permit
37 Condition II.C (Personnel Training), Permit Attachment 5 (Hanford Facility Personnel
38 Training Plan), and Addendum G (Personnel Training).
- 39

1
2
3
4

This page intentionally left blank.

DRAFT