

2. Remove outer gloves and protective suit and deposit in labeled container for disposable clothing.
3. Remove respirator, and place used respirator cartridges (if end of day) in container for disposable clothing.
4. If end of day, thoroughly clean respirator and store properly.
5. Remove inner gloves and discard into labeled container for disposable clothing.
6. Remove work boots without touching exposed surfaces, and put on street shoes. Put boots in individual plastic bag for later reuse.
7. Immediately wash hands and face using clean water and soap.
8. Shower as soon after work shift as possible.

## **B.8 DISPOSAL OF CONTAMINATED MATERIALS**

All disposable sampling equipment and materials will be placed inside of 10 mil polyethylene bags or other appropriate containers and placed in trash receptacles as directed by the client.

## **B.9 SITE SECURITY AND CONTROL**

Site security and control will be the responsibility of the Project Manager. The "buddy-system" will be used when working in designated hazardous areas. Any security or control problems will be reported to appropriate authorities.

## **B.10 SPILL CONTAINMENT**

Sources of bulk chemicals subject to spillage are not expected to be encountered in this project. Accordingly, spill containment plan is not required for this project.