EXHIBIT B

FINAL CLEANUP ACTION PLAN

WASHINGTON STATE
DEPARTMENT OF
ECOLOGY

FINAL CLEANUP ACTION PLAN

CITY PARCEL SITE

SPOKANE, WA

EASTERN REGIONAL OFFICE

TOXICS CLEANUP PROGRAM

AUGUST 2004

TABLE OF CONTENTS

TABLE OF CONTENTS i
LIST OF FIGURES iii
LIST OF TABLES iv
LIST OF ACRONYMS v
1.0 INTRODUCTION 1
1.1 The Cleanup Process and the Cleanup Action Plan 1
1.2 Purpose and Objectives 1
1.3 Declaration 2
1.4 Applicability 2
1.5 Administrative Record 2
2.0 BACKGROUND INFORMATION 3
2.1 Site Description 3
2.2 Site History 3
2.3 Site Physical Characteristics 4
2.3.1 Drainage Features and Utilities 4
2.3.2 Site Geology 5
2.3.3 Site Hydrogeology 5
3.0 NATURE OF CONTAMINATION 6
3.1 Surface Soils 6
3.2 Subsurface Soils 6
3.3 Ground Water 6
3.4 Contaminants and Media of Concern 7
3.5 Current and Potential Pathways of Exposure 7
4.0 CLEANUP STANDARDS 8
4.1 Soil Cleanup Levels 8
4.2 Land Use of the Site 9
4.3 Site Cleanup Standards 10
4.3.1 Site Cleanup Levels 10
4.3.2 Points of Compliance 12
5.0 MTCA'S SELECTION OF CLEANUP ACTIONS PROCESS 13
5.1 Minimum Requirements for Cleanup 13
5.2 Disproportionate Cost Analysis [WAC 173-3340-360 (3)(e)] 13
5.3 Reasonable Restoration Time Frame 14
5.4 Screening of Alternatives 15
5.5 Expectations for Cleanup Action Alternatives [WAC 173-340-370] 15
6.0 PROPOSED CLEANUP ALTERNATIVES 17
6.1 Cleanup Action Objectives 17
6.2 Estimated Volumes of PCB Contaminated Soils 17
6.3 Federal Regulations Governing Site PCB Remediation 17
6.4 State Regulations Governing PCBs 18
6.5 Summary of Feasibility Study Cleanup Alternatives 18
6.5.1 Alternative 1: Building Demolition, Capping and Institutional Controls 19

6.5.2 Alternative 2: Building Demolition, In-situ Solidification/Stabilization, and Institutional Controls 20
6.5.3 Alternative 3: Deferred Building Demolition, Excavation, Off-Site Disposal, and Institutional Controls 20
6.5.4 Alternative 4 Building Demolition, Excavation, Off-Site Disposal and Institutional Controls 21
6.5.5 Alternative 5: Building Demolition, Excavation, Off-Site Incineration, and Institutional Controls 22
7.0 EVALUATION AND COMPARISON OF ALTERNATIVES 23
7.1 Threshold Requirements 23
7.2 Other Requirements 24
7.3 Expectations for Cleanup Action Alternatives 26
8.0 SITE CLEANUP ACTION 27
8.1 Selected Cleanup Action 27
8.2 Evaluation of the Cleanup Action with Respect to MTCA Criteria 27
8.2.1 Threshold Requirements 27
8.2.2 Other Requirements 28
8.2.3 Expectations for Cleanup Action Alternatives 29
8.3 Implementation Schedule 29
9.0 REFERENCES 30