SLAG DISPOSAL BECKWITH PROPERTY SITE EXCAVATION PROJECT

SLAG DISPOSAL BECKWITH PROPERTY SITE SOUTH 218TH STREET AND 90TH AVENUE SOUTH KENT, WASHINGTON



REFERENCE: 7.5 MINUTE USGS QUADRANGLE KENT, WASHINGTON. DATED 1994



6/16/10 ISSUED FOR CONSTRUCTION DEW DATE DESCRIPTION CKD.

DRAWING INDEX

SHEET NO.	DRAWING TITLE	
CIVIL		
1	TITLE SHEET, SITE LOCATION MAP, AND DRAWING INDEX	
2	GENERAL NOTES, LEGEND, SYMBOLS, AND ABBREVIATIONS	
3	SITE PLAN	
4	EXCAVATION PLAN	
5	SLAG FILL LINE OF CROSS SECTIONS	
6	SLAG FILL CROSS SECTIONS	
7	FINAL GRADING PLAN	
8	FINAL GRADE LINE OF CROSS SECTIONS	
9	FINAL GRADE CROSS SECTIONS	
10	EROSION CONTROL PLAN	
11	DETAILS	
12	NOTES	
WETLAND		
W1	WETLAND BUFFER PLAN	
W2	PLANTING PLAN	
W3	PLANTING SPECIFICATIONS	



PREPARED FOR

EARLE M. JORGENSEN COMPANY 10650 ALAMEDA STREET LYNWOOD, CALIFORNIA 90262


SLAG DISPOSAL BECKWITH PROPERTY **EXCAVATION PROJECT** KENT, WASHINGTON


TITLE SHEET,


DRAWING INDEX


SCALE AS SHOWN PROJECT NO. 831-022 FILE NAME SHEET SET5.dwg SHEET NO. OF SITE LOCATION MAP, AND


ELECTRICAL ABBREVIATIONS STANDARD ABBREVIATIONS PIPING, ELECTRICAL AND EQUIPMENT SYMBOLS A/AMP GATE VALVE FEMALE ADAPTER GROUND AIR FILTER AGGREGATE BASE ALTERNATING CURRENT HIGH DENSITY POLYETHYLENE PRV PRESSURE RELEASE VALVE -1001-— GLOBE VALVE HORIZ. HORIZONTAL PSI PSIA POUNDS PER SQUARE INCH - S - SILENCER GROUND ROD (3/4* COPPER WELD) BD BUS DUCT ASPHALTIC CONCRETE HORSEPOWER/HIGH PRESSURE -M----- BALL VALVE POUNDS PER SQUARE INCH, ABSOLUTE APPROXIMATELY HOUR PSIG POUNDS PER SQUARE INCH, GAUGE CURRENT AIR FILTER — BUTTERFLY VALVE HEATER STRIP NEEDLE VALVE CIRCUIT BREAKER HYD HYDRANT PVC POLYVINYI CHLORIDI ---- CHECK VALVE HAND OFF AUTOMATIC CLG CEILING. BLIND FLANGE HOA (1) PV PR JUNCTION BOX, PB-PULLBOX B.G.S. BELOW GROUND SURFACE FLOW METER ID INSIDE DIAMETER DC DIRECT CURRENT RLDG BUILDING DIAPHRAGM OPERATED VALVE PUE PUBLIC UTILITY EASEMENT BOTTOM OF PIPE BALL VALVE INCHES - HOSE BIR KILOWATT HOUR METER DP DT DOUBLE POLE INVERT RADIUS/RISER CONC CONCRETE IPS IRON PIPE SIZE SOLENOID VALVE REINFORCED CONCRETE RC CPLG /CL CV COUPLING (M) MOTOR SAMPLE TAP/MONITORING PORT JT JB IOINT REQ REF EG ENCLOSED AND GASKETED CENTERLINE JUNCTION BOX MOTOR OPERATED VALVE REFERENCE CONTROL VALVE/CHECK VALVE E(OH) ELECTRICAL (OVERHEAD) E(UG) EMER ELECTRICAL (UNDERGROUND) KO KNOCK OUT HEAT EXCHANGER DC DOUBLE CONTAINED SCHEDULE MOTOR OVERLOAD EMERGENCY PRESSURE REGULATING VALVE LSHH LEVEL SWITCH Ø/DIA DIAMETER SDR STANDARD DIMENSION RATIO EPO EMT EMERGENCY POWER OFF DRAWING DWG DP DPI SECT SHT SPEC SQ STA STD STL SBO ST STR PRESSURE RELIEF OR AIR RELIEF SECTION MOTOR ELECTRICAL METALLIC TUBING DUAL PHASE SHEET Lh NON-FUSABLE DISCONNECT SWITCH EXP EXPOSED DIFFERENTIAL PRESSURE INDICATOR SPECIFICATION MH MJ MANHOLE SQUARE EACH FACE VACUUM RELIEF FRO FURNISHED BY OTHERS STATION WELD CAP PILOT LIGHT, R=RED, W=WHITE, G=GREEN EL/ELEV ELEVATION MIN MINUTE/MINIMUM FLEX FLEXIBLE METAL CONDUIT MISC MISCELLANEOUS MALE NATIONAL PIPE THREAD STANDARD FRN DUAL ELEMENT FUSE ELEC ELECTRICAL -3 SCREWED CAR ELB 0 SELECTOR SWITCH NORMALLY OPEN SUPPLIED BY OWNER MP METER PUMP AO=AUTO OFF, HOA=HAND OFF AUTO ETHYLENE PROPYLENE RUBBER GEN GENERATOR EPDM SAMPLE TAP MONITORING PORT EXIST/(E) EXP MON.POR GROUND FAULT INTERRUPTER FXISTING --M----- FLANGE SWITCH, 120-277V, 2-2POLE, 20A STRAINER EXPANSION GND GROUND NORMALLY CLOSED SS STL STAINLESS STEEL GRC GALVANIZED RIGID CONDUIT EW EA EACH WAY - I BLIND FLANGE NC NORMALLY CLOSED (T) STEEL SOIL VAPOR EXTRACTION NIC NO NOT IN CONTRACT SVE $\neg \triangleright$ - REDUCER/INCREASER HOA HAND-OFF-AUTO SWITCH X MAGNETIC STARTER FC FO FAIL CLOSE NORMALLY OPEN (TD) DIRECTION OF FLOW TIME DELAY RELAY, CR=CONTROL RELAY FAIL OPEN NO. NUMBER IRD INFRARED DETECTOR FLXC TYP ----ll------- UNION ww DUPLEX RECEPTACLE, 15A; TOP OF CASING/CURB TOC FLOW METER NTS NOT TO SCALE TRANSFORMER \Box HORSE POWER NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM -= $\sim\sim$ TOS TOP OF STEEL --- FLEXIBLE PIPE COUPLING WP-WEATHER PROOF CYCLES PER SECOND FT TOP OF WALL UNDERGROUND PULLBOX FUT FIN GR FUTURE OC ON CENTER JUNCTION BOX FINISHED GRADE BLOWER OR FAN UBC UNIFORM BUILDING CODE ETM ELAPSED TIME METER OUTSIDE DIAMETER OCCUPATIONAL SAFETY AND FLANGED END LIGPS UNDERGROUND PULL SECTION W.P. WEATHER PROTECTED LIQUID TIGHT FLEXIBLE OSHA LFMC FEMALE NATIONAL PIPE THREAD UTIL HEALTH ADMINISTRATION CENTRIFUGAL PUMP METAL CONDUIT OVHD FUSE 120/208V PANEL GA GAUGE GRANULAR ACTIVATED CARBON VALVE/VENT/VOLTS VACUUM VARIES/VARIABLE MOTOR/MOTOR STARTER COIL 目 #/LB PITOT TUBE POUND MCC MOTOR CONTROL CENTER GALV GI GALVANIZED PULL BOX 277/480V PANEL MCP MOTOR CIRCUIT PROTECTOR GALVANIZED IRON VERT VERTICAL PBF PROVIDED BY FARALLON GPM GR **GALLONS PER MINUTE** VP VRV STRAINER PC PCC FUSED DISCONNECT PORTLAND CEMENT NC NORMALLY CLOSED *HIGH LIGHT STANDARD VACUUM RELIEF VALVE GRADE PORTLAND CEMENT CONCRETE NATIONAL ELECTRIC CODE NEC GND GSKT GROUND W WITH TRAP GASKET W/O WITHOUT PROPERTY LINE/PIPE LINE MANUFACTURERS ASSOCIATION GROUNDWATER WATER SURFACE/WATER STOP REVISION TO PLANS GATE VALVE (AF) CAMLOCK CONNECTION NORMALLY OPEN PRESSURE NO OL. OVERLOADS DIAMETER VERTICAL PIPERUN PBS PUSHBUTTON **LEGEND** POWER FACTOR GENERAL NOTES PL PLC PROGRAMMABLE LOGIC CONTROLLER Para may mad RIGID CONDUIT RECEPTACLE RC LINE OF CROSS SECTION EXTENT OF SLAG 1. A COPY OF THE PROJECT DESIGN DRAWINGS AND SPECIFICATIONS SHALL BE MAINTAINED ON THE JOB SITE AT ALL RCPT SITE BOUNDARY SN SOLID NEUTRAL CLAY BARRIER 2. COPIES OF ALL PERMITS SHALL BE MAINTAINED ON THE JOB SITE AT ALL TIMES. THE CONTRACTOR SHALL SINGLE POLE CULVERT COMPLY WITH ALL PERMIT REQUIREMENTS SINGLE THROW CENTER LINE OF STORM/DRAINAGE DITCH, SW SWITCH FLOW DIRECTION 3. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL DIMENSIONS. GRAVEL TE/TRAN TRANSFORMER SANITARY SEWER CONNECTION 4.BURIED UTILITIES SHOWN ON THE DRAWINGS ARE FOR GENERAL INFORMATION ONLY, UTILITY LOCATIONS ARE UNDERFLOOR FENCE ----APPROXIMATE AND MAY NOT BE INCLUSIVE OF ALL LITH ITIES THAT EXIST ON THE PROPERTY EDGE OF WATER UG UNDERGROUND 60 ml HDPF LINER 5. THE CONTRACTOR SHALL HAVE A PRIVATE UTILITY LOCATE SERVICE VERIFY ALL UTILITIES AND MARK THEIR VFD VARIABLE FREQUENCY DRIVE 4" PVC PIPE LOCATIONS ON THE GROUND PRIOR TO STARTING CONSTRUCTION. FARALLON SHALL BE CONTACTED **GRAVEL SURFACE** VAPOR PROOF IMMEDIATELY IF A CONFLICT IS FOUND BETWEEN EXISTING UTILITIES AND THE PROJECT DESIGN WASTE WATER TREATMENT PVC PIPING WHT WHITE 6.FARALLON SHALL BE NOTIFIED OF DISCREPANCIES BETWEEN CONTRACT DRAWINGS AND ACTUAL SITE 00000 WEATHER PROOF ~~~~~ SILT FENCE CONSTRUCTION ENTRANCE ΧP **EXPLOSION PROOF** WETLAND BUFFER 7. THE CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR THE JOB SITE CONDITIONS AND ENSURE THE SAFETY OF IONAL ALL PERSONS AND PROPERTY FOR THE DURATION OF ON SITE PROJECT WORK. THE CONTRACTOR SHALL WETLAND FARALLON TEST PIT PROTECT STRUCTURES, UTILITIES, AND PAVING FROM DAMAGE, DIRECT OR INDIRECT, RESULTING FROM THE TP-10 STANDARD SYMBOLS WORK. THIS REQUIREMENT SHALL APPLY CONTINUOUSLY OVER THE DURATION OF ON SITE ACTIVITIES AND NOT BE LIMITED TO NORMAL WORKING HOURS DETAIL NUMBER SECOR TEST PIT SUMP 2 @ SUMF APPROXIMATE LOCATION CURRENT_36 8. ALL EXCAVATIONS SHALL BE PERFORMED IN STRICT ACCORDANCE WITH APPLICABLE U.S. DEPARTMENT OF LABOR REFERENCE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) AND THE WASHINGTON INDUSTRIAL SAFETY AND **X** 58.00 TOP OF SLAG ELEVATION SEEP HEALTH ACT (WISHA) REGULATIONS. THE CONTRACTOR ASSUMES FULL RESPONSIBILITY FOR THE SAFETY OF ALL [48.00] BOTTOM OF SLAG ELEVATION CONSTRUCTION OPERATIONS X 58.00 TOP OF SLAG ELEVATION TREE 9.NO TRENCHES SHALL BE LEFT OPEN WHEN WORK IS NOT IN PROGRESS. ALL OPEN EXCAVATIONS SHALL BE (48.00) **BOTTOM OF SLAG ELEVATION** FENCED PREPARED FOR SLAG DISPOSAL BECKWITH PROPERTY PREPARED BY AS SHOWN **EXCAVATION PROJECT** PROJECT NO 831-022 KENT, WASHINGTON EARLE M. JORGENSEN COMPANY FILE NAME: GENERAL NOTES. 10650 ALAMEDA STREET SHEET SET5.dwg 6/16/10 LEGEND.SYMBOLS. SHEET NO. OF ISSUED FOR CONSTRUCTION DEW HF RMFARALLON CONSULTING LYNWOOD, CALIFORNIA 90262 975 5th Avenue Northwest Issaguah, WA 98027 AND ABBREVIATIONS APP. DATE DESCRIPTION BY CKD.

























STABILIZED ACCESS SHALL BE USED IN ALL AREAS OF THE SITE WITH VEHICLE TRAFFIC AND PARKING, INCLUDING PLANTING STRIPS. OTHER MEANS OF PROVIDING STABILIZED ACCESS WILL BE CONSIDERED.


1 TYPICAL CONSTRUCTION ENTRANCE NOT TO SCALE








3 DITCH DETAIL NOT TO SCALE








BURY SHEETING IN 4 IN. X 6 IN. TRENCH A
MINIMUM OF 8 FT. SETBACK FROM TOP OF
SLOPE. BACKFILL WITH WASHED ROCK.

PROVIDE ENERGY DISSIPATION AT TOE WHEN
NEEDED.

TOE IN SHEETING IN 4 IN. X 6 IN. TRENCH A
MINIMUM OF 3 FT. SETBACK FROM BOTTOM
OF SLOPE. BACKFILL WITH WASHED ROCK.

CONVEY RUNOFF TO APPROVED LOCATION.

TYPICAL STOCKPILE
NOT TO SCALE



PREPARED BY



FARALLON CONSULTING 975 5th Avenue Northwest Issaquah, WA 98027 PREPARED FOR

EARLE M. JORGENSEN COMPANY 10650 ALAMEDA STREET LYNWOOD, CALIFORNIA 90262 SLAG DISPOSAL BECKWITH PROPERTY
EXCAVATION PROJECT
KENT, WASHINGTON

...,

TY SCALE
AS SHOWN
PROJECT NO.
831-022
FILE NAME:
SHEET SETS.dwg
SHEET NO. OF

 6/16/10
 ISSUED FOR CONSTRUCTION
 DEW
 HF
 RM

 DATE
 DESCRIPTION
 BY
 CKD.
 APP.

DETAILS

ANY EXCAVATIONS

- 1. CALL THE UNDERGROUND LOCATE LINE 1-800-424-5555 A MINIMUM OF 48 HOURS PRIOR TO
- 2. ALL UTILITIES SHOWN ON THE DRAWINGS ARE PRESENTED FOR GENERAL INFORMATION ONLY. THE UTILITIES SHOWN MAY NOT BE INCLUSIVE OF ALL UTILITIES THAT EXIST ON THE PROPERTY. UTILITY LOCATIONS ARE APPROXIMATE AND ARE NOT TO BE RELIED UPON DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATIONS OF ALL UTILITIES.
- 3. PERFORM SITE SURVEY TO ESTABLISH HORIZONTAL AND VERTICAL CONTROL AND MARK ESTIMATED EXCAVATION LIMITS BASED ON "ESTIMATED LIMITS OF SLAG CONTROL POINTS" TABLE, SHEET 4 OF 12. SURVEY SHALL BE PERFORMED BY A LICENSED SURVEYOR.
- 4. THE ESTIMATED LIMITS OF SLAG INDICATED ON THE DRAWINGS WAS DETERMINED BY EXCAVATION OF TEST PITS AND IS APPROXIMATE. THE ACTUAL EXTENT OF EXCAVATION REQUIRED TO REMOVE THE SLAG WILL BE DETERMINED BY THE ENGINEER IN THE FIELD.
- DO NOT DISTURB AREAS WITHIN 10 FEET OF STEEP SLOPES AS INDICATED ON THE DRAWINGS
- 6. INSTALL CONSTRUCTION STAKING AND FLAGGING TO DENOTE 10-FOOT BUFFER ZONE AROUND STEEP SLOPE AREAS. DO NOT IMPACT EXISTING VEGETATION WITHIN THE BUFFER ZONE OR STEEP SLOPE AREAS. IF SLAG IS DETERMINED TO EXTEND INTO BUFFER ZONE AT ANY LOCATION NOTIFY THE ENGINEER.
- 7. OVERBURDEN DETERMINED NOT TO HAVE BEEN IMPACTED BY THE SLAG, AS DESIGNATED BY THE ENGINEER, SHALL BE USED AS BACKFILL.
- 8. TURF AND WOOD DEBRIS OVERBURDEN SHALL BE SHREDDED AND CHIPPED PRIOR TO BEING USED AS BACKFILL
- 9. OVERBURDEN STOCKPILES SHALL BE COVERED WITH 8 MIL SHEET PLASTIC, AND WEIGHTED TO PREVENT WIND DISTURBANCE AND SEDIMENTATION.
- IMPLEMENT DUST CONTROL MEASURES AS REQUIRED TO PREVENT VISIBLE DUST FROM LEAVING THE SITE.
- 11. SLOPE EXCAVATION SIDEWALLS AS REQUIRED BY WASHINGTON ADMINISTRATIVE CODE 296-155-PART N, SAFETY STANDARDS FOR CONSTRUCTION WORK, EXCAVATION, TRENCHING, AND SHORING.
- 12. CONTRACTOR SHALL ASSIST THE ENGINEER IN COLLECTING SOIL SAMPLES FOR TESTING AS REQUIRED. SOIL SAMPLING WILL BE PERFORMED ON A 25-FOOT BY 25-FOOT CONTROL GRID. CONTRACTOR SHALL ESTABLISH AND MAINTAIN THE CONTROL GRID AT THE DIRECTION OF THE FINGINFER
- 13. MAINTAIN THE EXISTING INTERCEPTOR DRAIN ON THE EAST SIDE OF THE SITE OR MAKE ALTERNATE PROVISIONS TO DIRECT DRAINAGE AROUND THE SLAG.
- 14. EXISTING SURFACE WATER DRAINAGE SHALL BE MANAGED TO PREVENT CONTACT WITH SLAG TO THE EXTENT PRACTICABLE. SURFACE WATER THAT CONTACTS THE SLAG SHALL BE COLLECTED AND TREATED WITH THE EXISTING WATER TREATMENT SYSTEM.
- 15. GROUNDWATER ENCOUNTERED DURING SLAG EXCAVATION SHALL BE COLLECTED AND TREATED WITH THE EXISTING WATER TREATMENT SYSTEM.
- 16. WHERE EXISTING 60-MIL HDPE VERTICAL LINER AT EAST SIDE OF SLAG IS ENCOUNTERED REMOVE DOWN TO 2-FEET BELOW FINAL GRADE.
- 17. DO NOT DISTURB THE EXISTING DETENTION POND OR CLAY BARRIER.
- 18. DO NOT DISTURB EXISTING 4-INCH PVC DRAIN PIPE DISCHARGING TO THE DETENTION POND
- EXISTING DETENTION POND DISCHARGE CULVERT TO REMAIN. EXTENT OF SLAG IN THIS AREA IS UNKNOWN. IF CULVERT IS DAMAGED OR REMOVED DURING EXCAVATION OPERATIONS, IT IS TO BE REPLACED IN-KIND.
- 20. SLAG REMOVAL IN THE 'EXCAVATION CAUTION AREA' MAY EXTEND CLOSE TO THE 'STEEP SLOPE AREA'. AN OWNER PROVIDED GEOTECHNICAL ENGINEER OR ENGINEERING GEOLOGIST MUST BE PRESENT TO MONITOR THE WORK WHEN EXCAVATING IN THIS AREA. THE CONTRACTOR MAY BE REQUIRED TO EXCAVATE AND BACKFILL THIS AREA IN SECTIONS TO PREVENT IMPACTS TO STEEP SLOPES
- 21. CONTRACTOR SHALL PROVIDE THE ENGINEER WITH THE NAME OF THE PROPOSED DISPOSAL FACILITY FOR REVIEW PRIOR TO REMOVING ANY SLAG FROM THE SITE. THE CONTRACTOR IS ENCOURAGED TO PURSUE DISPOSAL AND RECYCLING ALTERNATIVES.
- 22. APPROXIMATELY 6-INCHES OF TOPSOIL COVERS THE EXISTING CAP. THE TOPSOIL SHALL BE STRIPPED AND RETAINED FOR USE IN SITE RESTORATION. THE CONTRACTOR SHALL BLEND TURF AND WOOD DEBRIS INTO THE STRIPPED TOPSOIL (SEE NOTE 8).
- 23. SECURITY SIREN AND FLASHING STROBE SHALL BE MAINTAINED BY THE CONTRACTOR
- 24. NIGHT TIME SECURITY PATROLS PROVIDED BY OWNER.

WATER TREATMENT NOTES

- 1. TWO WEEKS FOLLOWING NOTICE TO PROCEED THE CONTRACTOR SHALL BECOME RESPONSIBLE FOR THE OPERATION AND MAINTENANCE OF THE EXISTING WATER TREATMENT SYSTEM. RESPONSIBILITY FOR RENTAL OF THE 20,000 GALLON WATER STORAGE TANK, 25KVA GENERATOR, TEMPORARY TOILET, AND TEMPORARY COMPOUND FENCING WILL BE TRANSFERRED TO THE CONTRACTOR. THE CONTRACTOR SHALL PROVIDE 25 FEET OF JERSEY BARRIERS, FUEL TANK, AND FUEL FOR THE WATER TREATMENT SYSTEM OPERATION. THE WATER TREATMENT SYSTEM GENERATOR USES APPROXIMATELY 400 GALLONS OF FUEL PER MONTH. THE OWNER SHALL REMAIN RESPONSIBLE FOR RENTAL OF WATER TREATMENT SYSTEM INJECTOR EQUIPMENT, CO2 STORAGE EQUIPMENT, ELECTRONIC CONTROLS AND SUPPLY OF THE CO2.
- 2. CONTRACTOR SHALL COLLECT AND TREAT SURFACE WATER AND GROUNDWATER IMPACTED BY CONTACT WITH THE SLAG UTILIZING THE EXISTING WATER TREATMENT SYSTEM MODIFIED BY THE CONTRACTOR AS REQUIRED.
- WATER TREATMENT SYSTEM SHALL BE OPERATED IN COMPLIANCE WITH KING COUNTY INDUSTRIAL WASTE PROGRAM MAJOR DISCHARGE AUTHORIZATION NUMBER 4170-03, ISSUED JANUARY 12, 2010.
- CONSTRUCTION SHALL BE SEQUENCED TO MAINTAIN CONTINUOUS WATER TREATMENT OPERATIONS.
- WATER TREATMENT SYSTEM, INCLUDING SUMPS, SHALL BE MAINTAINED OPERATIONAL FOR A PERIOD OF 2 MONTHS FOLLOWING REMOVAL OF ALL SLAG MATERIAL.
- WATER TREATMENT SYSTEM OPERATION AND MAINTENANCE IS PERFORMED WEEKLY. WEEKLY VISITS ARE ESTIMATED TO BE 1-2 HOURS AND REQUIRE ONE LABORER.
- 7. THE WATER TREATMENT SYSTEM MAY BE RELOCATED TO ANY LOCATION ON THE SITE THAT IS AWAY FROM THE ROAD AND NOT LOCATED WITHIN THE STEEP SLOPE AREAS.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE RE-WIRING ELECTRICAL COMPONENTS OF THE WATER TREATMENT SYSTEM DURING SYSTEM RELOCATIONS.
- UPON COMPLETION OF THE EXCAVATION ACTIVITIES, THE WATER TREATMENT SYSTEM PIPING AND ELECTRICAL CONDUIT SHALL BE BURIED.

SITE GRADING AND RESTORATION NOTES

- FOLLOWING REMOVAL OF THE SLAG, AS CONFIRMED BY SOIL SAMPLING AND ANALYSIS PERFORMED BY THE ENGINEER, THE SITE SHALL BE BACKFILLED AND GRADED USING STOCKPILED NON-SLAG IMPACTED OVERBURDEN MATERIAL.
- BACKFILL OPERATIONS MAY BE SEQUENCED TO BACKFILL PORTIONS OF THE SITE WHILE EXCAVATING OTHERS.
- BACKFILL SHALL BE PLACED IN 1-FOOT LOOSE LIFTS AND COMPACTED TO A MINIMUM OF 85% OF MAXIMUM DENSITY AS DETERMINED BY THE STANDARD PROCTOR TEST (ASTM D698).
- 4. THE SITE SHALL BE REGRADED TO FOLLOW THE DRAINAGE PATTERN SHOWN ON THE DRAWINGS. IT IS ANTICIPATED THAT FINAL GRADE MAY VARY FROM THE LINES AND GRADES SHOWN ON THE DRAWING DUE TO VARIATIONS IN ACTUAL EXCAVATION QUANTITIES FROM ESTIMATED QUANTITIES.
- 5. DRAINAGE DITCHES SHALL BE INSTALLED TO DIRECT SURFACE WATER RUNOFF AS SHOWN.
- 6. HYDROSEED ALL DISTURBED AREAS USING A HYDROSEED/MULCH BLEND DESIGNED FOR USE IN WESTERN WASHINGTON. THE HYDROSEED/MULCH MIX SHALL INCLUDE A BONDED FIBER MATRIX TO PREVENT EROSION. SUBMIT PROPOSED HYDROSEED/MULCH BLEND FOR APPROVAL BY ENGINEER PRIOR TO APPLICATION.
- FOLLOWING COMPLETION OF WATER TREATMENT OPERATIONS (ESTIMATED TO BE 2 MONTHS
 AFTER THE COMPLETION OF THE SLAG REMOVAL) DEMOBILIZE TREATMENT EQUIPMENT,
 REMOVE ALL SUMPS, CONDUIT AND PIPING INCLUDED ALL BURIED PIPING, RESTORE
 DISTURBED AREAS, AND HYDROSEED.
- FOLLOWING SITE GRADING AND BACKFILL COMPACTION, THE CONTRACTOR SHALL SPREAD THE RETAINED TOPSOIL IN AN EVEN SIX INCH COVER OVER DISTURBED AREAS. ANY EXCESS TOPSOIL WILL BE PLACED IN WETLAND RESTORATION AREA.
- 9. THE SOURCE OF ALL IMPORT MATERIAL, INCLUDING DRAIN ROCK, CRUSHED ROCK, AND ANY OTHER FILL MATERIAL MUST BE APPROVED BY THE ENGINEER TWO WEEKS PRIOR TO PLACEMENT. THE ENGINEER MAY REQUIRE TESTING PRIOR TO MATERIAL ACCEPTANCE. THE COST OF ANY TESTING REQUIRED FOR MATERIAL ACCEPTANCE IS NOT INCLUDED IN THE CONTRACT PRICE.
- 10. THE CONTRACTOR SHALL PREPARE AN AS-BUILT SURVEY AT THE COMPLETION OF THE SITE RESTORATION WORK. THE AS-BUILT SURVEY SHALL BE PREPARED BY A LICENSED SURVEYOR
- 11. THE ACCESS ROAD WIDTH SHALL NOT EXTEND BEYOND THE EXISTING FOOTPRINT.


6/16/10 ISSUED FOR CONSTRUCTION DEW HF RM DATE DESCRIPTION BY CKD. APP.

EROSION CONTROL NOTES

- 1. ON-SITE EROSION CONTROL MEASURES SHALL BE THE RESPONSIBILITY OF THE
- 2. IN CASE EROSION OR SEDIMENTATION OCCURS TO ADJACENT PROPERTY, ALL CONSTRUCTION WORK WITHIN THE SITE THAT WILL AGGRAVATE THE SITUATION MUST CEASE AND THE CONTRACTOR SHALL IMMEDIATELY COMMENCE ON-SITE RESTORATION OR MITIGATION MEASURES. RESTORATION ACTIVITY SHALL CONTINUE UNTIL SUCH TIME AS THE PROBLEM IS RECTIFIED.
- ALL EROSION AND SEDIMENTATION CONTROL DEVICES SHOWN ON THE DRAWINGS SHALL BE INSTALLED PRIOR TO OR AS PART OF THE FIRST STAGE OF SITE PREPARATION.
- 4. SHOULD THE TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES AS SHOWN ON THIS DRAWING NOT PROVE ADEQUATE TO CONTROL EROSION AND SEDIMENTATION, THE CONTRACTOR SHALL INSTALL ADDITIONAL FACILITIES AS NECESSARY TO PROTECT ADJACENT PROPERTIES, SENSITIVE AREAS, NATURAL WATER COURSES, AND/OR STORM DRAINAGE SYSTEMS.
- ALL NECESSARY EROSION CONTROL FACILITIES SHALL BE PROPERLY MAINTAINED TO PREVENT DEBRIS, DUST, AND MUD FROM ACCUMULATING ON THE PUBLIC RIGHT-OF-WAY.
- SHOULD ANY DEBRIS, DUST, OR MUD ACCUMULATE IN THE PUBLIC RIGHT-OF-WAY THE CONTRACTOR SHALL PROVIDE FOR SWEEPING SERVICES AS REQUIRED TO CLEAN THESE AREAS.
- 7. ALL LAND DISTURBING ACTIVITY IS SUBJECT TO PROVISIONS OF THE CITY OF KENT STORMWATER MANAGEMENT REGULATIONS. SPECIFIC REQUIREMENTS TO BE FOLLOWED AT THE SITE INCLUDE:
- a) PROTECT ADJACENT PROPERTIES FROM ANY INCREASED RUNOFF OR SEDIMENTATION DUE TO THE CONSTRUCTION THROUGH THE USE OF BEST MANAGEMENT PRACTICES (BMPs), INCLUDING BUT NOT LIMITED TO, SEDIMENT TRAPS, SEDIMENT PONDS, FILTER FABRIC FENCES, VEGETATIVE BUFFER STRIPS AND BIO-ENGINEERED SWALES.
- b) CONSTRUCTION ACCESS TO THE SITE SHALL BE LIMITED TO ONE ENTRANCE CONSTRUCTED AT THE SOUTHWEST CORNER OF THE SITE. STABILIZE THE ENTRANCE WITH QUARRY SPALLS TO PREVENT SEDIMENT FROM LEAVING THE SITE OR ENTERING STORM DRAINS.
- c) INSTALL AND OPERATE A DECONTAMINATION PAD AS REQUIRED TO CLEAN VEHICLES LEAVING THE SITE AND PREVENT SEDIMENT FROM LEAVING SITE OR ENTERING STORM DRAINS.
- d) PREVENT SEDIMENT, CONSTRUCTION DEBRIS, PAINTS, SOLVENTS, ETC. OR OTHER TYPES OF POLLUTION FROM ENTERING STORMWATER DRAINAGE SYSTEMS.
- e) ALL EXPOSED SOILS SHALL REMAIN DENUDED FOR NO LONGER THAN SEVEN (7) DAYS AND SHALL BE STABILIZED WITH MULCH, HAY OR THE APPROPRIATE GROUND COVER. ALL EXPOSED SOILS SHALL BE COVERED IMMEDIATELY DURING ANY RAIN EVENT.
- f) HYDROSEED AND MULCH ENTIRE SITE UPON COMPLETION OF WORK OR IF WORK CEASES FOR MORE THAN TEN (10) DAYS. OTHER PROTECTION MEASURES MAY BE ACCEPTABLE IF APPROVED BY THE CITY OF KENT.
- 8. CONTRACTOR SHALL BE AVAILABLE FOR A PRE-CONSTRUCTION CONFERENCE WITH A CITY OF KENT REPRESENTATIVE TO DISCUSS IMPLEMENTATION AND MAINTENANCE OF PROJECT EROSION CONTROL FEATURES.
- ALL EROSION CONTROL MEASURES AND FACILITIES SHALL BE CLEANED OF ALL CONSTRUCTION DEPOSITS OR DEBRIS PRIOR TO FINAL COMPLETION OF THE CLEANUP ACTION.
- 10. A CONSTRUCTION STORMWATER GENERAL PERMIT APPLICATION WILL BE SUBMITTED BY THE ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLYING TO ALL PERMIT REQUIREMENTS WHICH INCLUDE PREPARING THE STORMWATER POLLUTION PREVENTION PLAN AND PROVIDING A CERTIFIED EROSION AND SEDIMENT CONTROL LEAD TO PERFORM SITE INSPECTIONS WEEKLY OR WITHIN 24 HOURS OF ANY DISCHARGE FROM THE SITE

SILT FENCE CONSTRUCTION NOTES

- 1. FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL AND CUT TO THE LENGTH OF THE BARRIER TO AVOID USE OF JOINTS. WHEN JOINTS ARE NECESSARY, FILTER CLOTH SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6-INCH OVERLAP, AND SECURELY FASTENED AT BOTH ENDS TO POSTS.
- 2. POSTS SHALL BE SPACED A MINIMUM OF 6 FEET APART AND DRIVEN SECURELY INTO THE GROUND (MINIMUM OF 30 INCHES).
- 3. A TRENCH SHALL BE EXCAVATED APPROXIMATELY 8 INCHES WIDE AND 12 INCHES DEEP ALONG THE LINE OF POSTS AND UPSLOPE FROM THE BARRIER. THIS TRENCH SHALL BE BACKFILLED WITH WASHED GRAVEL, OR COMPACTED NATIVE SOIL.
- 4. WHEN STANDARD STRENGTH FILTER FABRIC IS USED, A WIRE MESH SUPPORT FENCE SHALL BE FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS USING HEAVY-DUTY WIRE STAPLES AT LEAST 1 INCH LONG, TIE WIRES, OR HOG RINGS. THE WIRE SHALL EXTEND INTO THE TRENCH A MINIMUM OF 4 INCHES AND SHALL NOT EXTEND MORE THAN 24 INCHES ABOVE THE ORIGINAL GROUND SURFACE.
- 5. STANDARD STRENGTH FILTER FABRIC SHALL BE STAPLED OR WIRED TO THE FENCE, AND 20 INCHES OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NOT EXTEND MORE THAN 24 INCHES ABOVE THE ORIGINAL GROUND SURFACE. FILTER FABRIC SHALL NOT BE STAPLED TO EXISTING TREES.
- 6. WHEN EXTRA-STRENGTH FILTER FABRIC AND CLOSER POST SPACING IS USED, THE WIRE MESH SUPPORT FENCE MAY BE ELIMINATED. IN SUCH A CASE, THE FILTER FABRIC IS STAPLED OR WIRED DIRECTLY TO THE POSTS WITH ALL OTHER PROVISIONS OF ABOVE NOTES APPLYING.
- 7. FILTER FABRIC FENCES SHALL NOT BE REMOVED
 BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY
 STABILIZED
- CLEAN AND PROVIDE REGULAR MAINTENANCE OF THE SILT FENCE. THE SILT FENCE IS TO REMAIN VERTICAL AND IS TO FUNCTION PROPERLY THROUGH THE DURATION OF THE PROJECT.



PREPARED BY

FARALLON CONSULTING 975 5th Avenue Northwest Issaquah, WA 98027 PREPARED FOR


EARLE M. JORGENSEN COMPANY 10650 ALAMEDA STREET LYNWOOD, CALIFORNIA 90262 SLAG DISPOSAL BECKWITH PROPERTY EXCAVATION PROJECT


KENT, WASHINGTON

NOTES

PROJECT NO. 831-022 FILE NAME: SHEET SET5.dwg SHEET NO. OF

AS SHOWN







PLANTING SEQUENCE / NOTES:

- 1. STRIP ORGANIC SOIL AND STOCKPILE SEPARATELY FROM SLAG AND OVERBURDEN.
- 2. RIP, DISC, OR SCARIFY SUBGRADE SOILS TO A MINIMUM DEPTH OF 12 INCHES. DO NOT SCARIFY WITHIN DRIP LINE OF EXISTING TREES TO BE RETAINED.
- 3. PLACE 8" OF STOCKPILED SOILS AND 4" OF IMPORTED TOPSOIL WTIHIN WETLAND BUFFER PLANTING AREA.
- 4. DIG PLANTING PIT THAT IS AT LEAST TWICE THE DIAMETER OF CONTAINER, REMOVE ALL ROCKS, ROOTS, STICKS AND OTHER DEBRIS LARGER THAN 1" DIAMETER, SCARIFY THE PLANTING PIT BOTTOM AND SIDES TO A DEPTH OF 4 INCHES.
- 5. SET PLANT MATERIAL IN THE PLANTING PIT TO PROPER GRADE AND ALIGNMENT. SET PLANTS UPRIGHT, PLUMB, AND FACED TO GIVE THE BEST APPEARANCE OR RELATIONSHIP TO EACH OTHER. SET CROWN OF PLANT MATERIAL AT THE FINISH GRADE. NO FILLING WILL BE PERMITTED AROUND TRUNKS OR STEMS. BACKFILL THE PLANTING PIT WITH SOIL. DO NOT USE MUDDY MIXTURES FOR BACKFILLING.
- 6. SPACE PLANTS USING TRIANGULAR SPACING IN ACCORDANCE WITH PLANT SCHEDULE DIMENSIONS. PLANT GROUND COVERS TO WITHIN 18" OF THE TRUNKS OF TREES AND SHRUBS WITHIN PLANTING AREA AND TO WITHIN 12" OF THE EDGE OF PLANTING AREA. PLANT SHRUBS WITHIN 5' OF THE TRUNKS OF TREES WITHIN PLANTING AREA AND TO WITHIN 3' OF THE EDGE OF PLANTING AREA.
- 7. SHAPE SOIL TO PROVIDE WATERING RING WITH A DIAMETER EQUAL TO 2X THE CONTAINER WIDTH.
- 8. MULCH PLANTING BEDS IMMEDIATELY AFTER PLANTING. THOROUGHLY WATER MULCHED AREA. AFTER WATERING, RAKE MULCH TO PROVIDE A UNIFORM FINISHED SURFACE.

PLANTING SCHEDULE / LEGEND





TREE & SHRUB PLANTING ON SLOPES

TYPICAL GROUND COVER PLANTED AT NURSERY -MIN 4-6" MULCH FINISH GRADE -8" STOCKPILED ORGANIC SOIL AND 4" IMPORTED TYPICAL SPACING TOPSOIL (PER PLANT SCHEDULE)-

GROUNDCOVER PLANTING

EXISTING WETLAND PREVIOUSLY RESTORED WITH NATIVE PLANTS

ISSUED FOR CONSTRUCTION 6/15/10 BMB PH 6/15/10 CKD. APP. DATE DESCRIPTION

CONTOUR INTERVAL: 2 FOOT



PREPARED FOR

EARLE M. JORGENSEN COMPANY 10650 ALAMEDA STREET LYNWOOD, CALIFORNIA 90262

SLAG DISPOSAL BECKWITH PROPERTY SITE KENT, WASHINGTON

PLANTING PLAN

SCALE AS SHOWN PROJECT NO. 831-022 FILE NAME: 00224-PL-002.dwg SHEET NO. OF

PLANTING SPECIFICATIONS

Submittals

- 1. Topsoil analysis results of a 5 pound bag from soils testing laboratory, indicate source and obtain Owner's approval before hauling topsoil to site.
- 2. Source of the mulch supply and a 1 gallon sample for approval before installation.
- 3. List of nurseries supplying all plant species with Name and phone number of contact person. Submit representative color, dated photographs of each plant species

Notifications

Notify the Owner at least five working days prior to the installation of plant material.

Products:

Topsoil

The Topsoil shall consist of 60 percent Sand Component and 40 percent Composted Organic Amendment by volume and shall meet or exceed the following specifications:

The Sand Component shall meet the following specifications within reasonable variations:

Screen Size	Percent Passi
6.35 mm	95
#10	85
#30	50
#60	40
#100	20
#200	10

The Composted Organic Soil Amendment shall consist of 100 percent decomposed organic mulch material, and shall consist of yard waste debris or other organic waste materials that have been sorted, ground up, aerated, and aged, and shall be fully composted, stable, and mature (non-aerobic). The composting process shall be for at least 6 months' time and the organic amendment shall have a uniform dark, soil-like appearance and consist of 100 percent recycled content. In addition, the organic amendment shall have the following physical characteristics:

- 1. Shall be certified by the Process to Further Reduce Pathogens (PFRP) guideline for hot composting as established by EPA. Shall be fully mature and stable before usage
- 2. Shall be screened using a sieve no finer than 1/4-inch and no greater than 1/2-inch. Based on dry weight of total organic amendment sample, it must comply with the following percent by weight passing:

Sieve Size	Maximum %	Minimum %	
12.7 mm (1/2 inch)	0	100	
6.35 mm (1/4 inch)	100	95	
4.76 mm	100	90	
2.38 mm	100	75	
1.00 mm	45	70	
500 micron	30	0	

- 3. Meets "composted materials" definition in WAC 173-350 Section 220, available at: http://www.ecy.wa.gov/programs/swfa/compost/
- Has Organic Matter Content 35 to 65 percent and Carbon to Nitrogen ratio of 25:1.
- Shall have heavy metal concentrations below the Washington State Department of Agriculture (WSDA) per year load limits as follows:

Metal	WSDA-Maxium pounds per acre per year
Arsenic	0.297
Cadmium	0.079
Cobalt	0.594
Lead	1.981
Mercury	0.019
Molybdenum	0.079
Nickel	0.713
Selenium	0.055
Zinc	7.329

6. Shall be certified by PFRP guidelines for composting as established by the U.S. Environmental Protection Agency (EPA).

PLANTING SPECIFICATIONS CONTINUED

The topsoil mix shall also have the following characteristics;

- 1. The pH range shall be from 5.5 to 7.5.
- The Sodium Adsorption Ratio shall be less than 6.0.
- The Saturation Extract Concentration of Boron shall be less than 1.0 part per million (ppm).
- The Water Percolation/Infiltration Rate of the disturbed soil sample shall be a minimum of 0.4 inches per hour.
 - The Soll Structure shall be loose, friable, and not subject to consolidation or compaction.
- The soil mix shall contain less than 100 plant parasitic nematodes per 100 cubic centimeters (cc) of soil.
- The soil mix shall be relatively free of soil-borne plant pathogens.
- 8. Minimal weed seed shall be present, based on germination testing of a representative sample.
- Non-soil components shall be less than 1 percent by volume (i.e., plastic, sticks, glass, etc.).
- 10. The Final Topsoil Mix shall contain sufficient quantities of available nitrogen, phosphorus, potassium, calcium, magnesium, sulfate, copper, zinc, manganese, iron, and boron to support normal plant growth. In the event of nutrient inadequacies, provisions shall be made to add required materials prior to planting.

Bark or wood chip mulch shall be derived from Douglas fir, pine, or hemlock species. It shall be ground so that a minimum of 95% of the material will pass through a 2-inch sieve and no more than 25%, by loose volume, will pass through a No. 4 sieve. The mulch shall not contain resin, tannin, or other compounds in quantities that would be detrimental to plant life. Sawdust or wood shavings shall not be used as mulch.

Plants:

All plants shall by nursery grown and from a nursery with similar climatic conditions to the locality of the project. Stock furnished shall be at least the minimum size indicated

Provide only sound, healthy, vigorous plants free from weeds, defects, sunscald injuries, and abrasions of the bark, plant diseases, insect eggs, borers, and all forms of infestation. All plants shall have a fully developed form without voids, open spaces, broken branches, flush cuts or stubs. No plants shall be loose in the container or not bound.

Plants shall be packed and transported with care. If plants cannot be planted immediately upon delivery, properly protect them with soil, wet peat moss, or in a manner acceptable to the Owner. Water heeled in plantings daily.

Plant material shall be inspected and approved by the Consultant and the Owner on site prior to installation. Remove unsatisfactory

Stock shall not be installed when ambient temperatures are below 35 degrees F or above 80 degrees, or when wind velocity exceeds 30

Warrant plant material to remain alive and be in healthy, vigorous condition for a period of one year after the date of Physical Completion.

Maintain planting until acceptance by Owner. Maintenance shall include cultivating, weeding, watering, pruning (only as directed), and application of appropriate insecticides and fungicides necessary to maintain plants free of insects and disease

Reset settled plants to proper grade and position. Restore planting watering ring and adjacent material and remove dead material.

Water trees, shrub, and ground cover beds within the first 24 hours of initial planting, and not less than twice per week (including rain) until Physical Completion.

Physical Completion:

Inspection to determine Physical Completion of planted areas will be made by the Owner, upon the Contractor's request. Provide notification at least 10 working days before requested inspection date

Planted areas will be accepted provided all requirements, including the maintenance period have been complied with and plant materials are alive and in a healthy vigorous condition

Upon Physical Completion, the Owner will assume plant maintenance.





PREPARED FOR

EARLE M. JORGENSEN COMPANY 10650 ALAMEDA STREET LYNWOOD, CALIFORNIA 90262

SLAG DISPOSAL BECKWITH PROPERTY SITE SCALE AS SHOWN KENT WASHINGTON

PLANTING SPECIFICATIONS

PROJECT NO. 831-022 FILE NAME: 100224-PL-002.dwg SHEET NO.

6/15/10 ISSUED FOR CONSTRUCTION BMB PH 6/15/10 CKD. DATE DESCRIPTION BY APP

CONTOUR INTERVAL: 2 FOOT