TABLE 2 (PAGE 1 OF 3)
SUMMARY OF SOIL FIELD SCREENING AND PAH CHEMICAL ANALYTICAL RESULTS
CLEANUP CONFIRMATION SAMPLES
THOMAS OIL SITE/NW MARITIME CENTER
PORT TOWNSEND, WASHINGTON

Soil Sample Number - Depth Sampled[1] (feet bgs)	Date Sampled	Sample Location	Field Screening Results[1]		Noncarcinogenic PAHs[2] (mg/kg)											Carcinogenic PAHs[2] (mg/kg)							Sum of cPAHs
			Headspace Vapors (ppm)	Sheen	Acenaphthene	Acenaphthylene	Anthracene	Benzo (ghi) perylene	Fluoranthene	Fluorene	1-Methylnaphthalene	2-Methylnaphthalene	Naphthalene	Phenanthrene	Pyrene	Benzo (a) anthracene	Benzo (a) pyrene	Benzo (b) fluoranthene	Benzo (k) fluoranthene	Chrysene	Dibenz (a,h) anthracene	Indeno (1,2,3-cd) pyrene	
Excavation 1--Unocal Tank Farm																							
Ex1-1-1.0[3]	06/24/02	Northeast Wall	37	SS	**PAHs not analyzed - see Table 1 for details**																		
Ex1-2-6.0[3]	06/24/02	Southeast Wall	97	HS	<2.00	<2.00	<2.00	<2.00	<2.00	<2.00	51.6	26.6	37.5	<2.00	<2.00	<2.00	<2.00	<2.00	<2.00	<2.00	<2.00	<2.00	ND
Ex1-3-7.0[3]	06/24/02	Southeast Wall	100	HS	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	20.9	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	ND
Ex1-4-10.0	06/24/02	East Base	97	MS	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	0.0149	0.0149	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-5-10.0	06/24/02	Southeast Base	72	MS	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-6-11.0	06/24/02	Southeast Base	61	MS	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	0.0129	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-7-10.0	06/24/02	South Base	64	MS	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	0.0148	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-8-10.0	06/24/02	Northeast Base	73	MS	0.0123	<0.0100	0.0108	<0.0100	<0.0100	0.0152	0.0202	0.0173	0.0101	0.0123	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-9-11.0	06/24/02	Central Base	69	MS	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-10-11.0	06/24/02	Central Base	54	MS	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	0.0404	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-11-10.0	06/24/02	Southwest Base	54	MS	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	0.0191	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-12-9.0	06/24/02	Northeast Wall	92	HS	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	0.0355	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-13-6.0[3]	06/25/02	Northeast Wall	57	HS	4.85	<0.500	<0.500	<0.500	2.26	8.86	39.3	<0.500	<0.500	17.4	1.90	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	ND
Ex1-14-6.0[3]	06/25/02	North Wall	43	MS	<0.200	<0.200	1.83	<0.200	<0.200	8.13	21.1	<0.200	<0.200	13.4	0.631	<0.200	<0.200	<0.200	<0.200	<0.200	<0.200	<0.200	ND
Ex1-15-7.0	06/25/02	North Wall	62	MS	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-16-10.0[3]	06/25/02	North Base	71	MS	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	0.0175	<0.0100	<0.0100	0.0160	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-17-10.0	06/25/02	North Base	79	MS	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-18-7.0[3]	06/25/02	Northeast Wall	53	MS	<1.00	<1.00	<1.00	<1.00	2.60	<1.00	60.4	<1.00	<1.00	21.1	2.01	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	ND
Ex1-19-7.0[3]	06/25/02	Northeast Wall	47	HS	4.96	<0.500	<0.500	<0.500	<0.500	<0.500	71.0	<0.500	<0.500	20.5	1.24	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	ND
Ex1-20-11.0	06/25/02	North Base	69	MS	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	0.0706	0.0209	<0.0100	0.117	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-21-10.0	06/25/02	Northwest Base	71	MS	<0.0100	<0.0100	0.0106	<0.0100	<0.0100	<0.0100	0.2110	<0.0100	<0.0100	0.0626	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-22-9.0[3]	06/25/02	West Wall	70	MS	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	63.1	34.4	12.9	12.8	1.38	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	ND
Ex1-23-10.0[3]	06/26/02	Southwest Base	74	MS	1.43	<0.400	<0.400	<0.400	1.15	3.25	29.8	7.53	9.59	5.07	0.698	<0.400	<0.400	<0.400	<0.400	<0.400	<0.400	<0.400	ND
Ex1-24-10.0	06/26/02	Northeast Base	62	MS	<0.0100	<0.0100	0.0110	<0.0100	0.0181	<0.0100	<0.0100	<0.0100	<0.0100	0.0626	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-25-10.0[3]	06/26/02	Central Base	50	MS	0.0201	<0.0100	<0.0100	<0.0100	0.0372	<0.0100	<0.0100	<0.0100	<0.0100	0.0327	0.0253	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-26-10.0	06/26/02	Central Base	<100	MS	<0.0100	<0.0100	0.0110	<0.0100	0.0572	<0.0100	<0.0100	<0.0100	<0.0100	0.0798	0.0482	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-27-10.0	06/26/02	Southwest Base	<100	MS	<0.0100	<0.0100	0.0162	<0.0100	0.0132	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-28-7.0[3]	06/26/02	Northwest Wall	<100	HS	<0.0100	<0.0100	<0.0100	0.0116	<0.0100	0.327	4.66	<0.0100	<0.0100	0.476	0.116	0.0160	<0.0100	0.0363	0.0421	0.0123	<0.0100	<0.0100	0.107
Ex1-29-7.0	06/26/02	Southwest Wall	<100	HS	<0.0100	<0.0100	<0.0100	<0.0100	0.0386	0.136	4.29	<0.0100	0.321	0.1110	0.0205	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Ex1-30-7.0	06/26/02	Southwest Wall	<100	HS	<0.200	<0.200	0.416	<0.200	0.400	1.45	84.1	7.87	33.4	0.954	0.200	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	<0.0100	ND
Cleanup Action Level					NA											NA							1.0

Notes appear on page 3 of 3.