

**Table A-1 - Remedial Action Alternative B**

Natural Recovery with Limited Capping  
 Whatcom Waterway Area

Item	Unit	Unit Cost	No. of Units	Total Cost
<b><i>Mobilization/Demobilization</i></b>	PERCENT	2%	\$2,313,000	\$35,000
<b><i>Outer/Mid Whatcom Waterway - SSU 1</i></b>				
- No Action	-	-	-	-
<b><i>Head of Whatcom Waterway (30' Channel) - SSU 2</i></b>				
- No Action	-	-	-	-
<b><i>Head of Whatcom Waterway (18' Channel) - SSU 3</i></b>				
- No Action	-	-	-	-
<b><i>G-P Log Pond - SSU 4</i></b>				
- Maintain existing Interim Action cap	-	-	-	-
<b><i>G-P ASB - SSU 5</i></b>				
- Cap	CY	\$15.0	117,200	\$1,758,000
<b><i>Port Log Rafting Area - SSU 6</i></b>				
- No Action	-	-	-	-
<b><i>Starr Rock - SSU 7</i></b>				
- Cap	CY	\$15.0	37,000	\$555,000
<b><i>I&amp;J Street Waterway - SSU 8</i></b>				
- No Action	-	-	-	-
<b><i>Disposal - No Material is Generated</i></b>				
- Not Applicable	-	-	-	-
<b><i>Engineering Design</i></b>	PERCENT	10%	\$2,313,000	\$231,000
<b><i>Construction Monitoring/Management</i></b>	PERCENT	5%	\$2,313,000	\$116,000
<b><i>Long-term Monitoring</i></b>	LS	\$300,000	1	\$300,000
<b><i>Contingency</i></b>	PERCENT	30%	\$2,995,000	\$899,000
<b>TOTAL ESTIMATED COST</b>				<b>\$3,894,000</b>