

**Table A-7 - Remedial Action Alternative H**

Full Removal from Navigation Areas and Partial Removal from G-P ASB Area w/ Upland Disposal (Pilot No. 2D)  
 Whatcom Waterway Area

Item	Unit	Unit Cost	No. of Units	Total Cost
<b>Mobilization/Demobilization</b>	PERCENT	2%	\$51,222,000	\$768,000
<b>Outer/Mid Whatcom Waterway - SSU 1</b>				
- Cap	CY	\$15.0	0	\$0
- Mechanical Dredge and Transport to Upland Offload Facility	CY	\$5.0	570,000	\$2,850,000
<b>Head of Whatcom Waterway (30' Channel) - SSU 2</b>				
- Cap	CY	\$15.0	34,100	\$512,000
- Mechanical Dredge and Transport to Upland Offload Facility	CY	\$5.0	80,000	\$400,000
<b>Head of Whatcom Waterway (18' Channel) - SSU 3</b>				
- Cap	CY	\$15.0	0	\$0
- Mechanical Dredge and Transport to Upland Offload Facility	CY	\$5.0	40,000	\$200,000
<b>G-P Log Pond - SSU 4</b>				
- Maintain existing Interim Action cap	-	-	-	-
<b>G-P ASB - SSU 5</b>				
- Cap	CY	\$15.0	77,700	\$1,166,000
- Mechanical Dredge and Transport to Upland Offload Facility	CY	\$5.0	200,000	\$1,000,000
<b>Port Log Rafting Area - SSU 6</b>				
- Cap	CY	\$15.0	48,700	\$731,000
- Mechanical Dredge and Transport to Upland Offload Facility	CY	\$5.0	60,000	\$300,000
<b>Starr Rock - SSU 7</b>				
- Cap	CY	\$15.0	107,500	\$1,613,000
- Mechanical Dredge and Transport to Upland Offload Facility	CY	\$15.0	130,000	\$1,950,000
<b>I&amp;J Street Waterway - SSU 8</b>				
- No Action	-	-	-	-
<b>Disposal - Upland</b>				
- Offload, Haul, and Place at Roosevelt Regional Landfill	CY	\$37.5	1,080,000	\$40,500,000
<b>Engineering Design</b>	PERCENT	10%	\$51,222,000	\$5,122,000
<b>Construction Monitoring/Management</b>	PERCENT	5%	\$51,222,000	\$2,561,000
<b>Long-term Monitoring</b>	LS	\$500,000	1	\$500,000
<b>Contingency</b>	PERCENT	30%	\$60,173,000	\$18,052,000
<b>TOTAL ESTIMATED COST</b>				<b>\$78,225,000</b>