CHRISTINE GREGOIRE
Director

STATE OF WASHINGTON
DEPARTMENT OF ECOLOGY
106 South 6th Ave. • Yakima, Washington 98902-3387 • (509) 575-2490

October 10, 1991

Mr. Gerald L. Copp
Chief Executive Officer
General Manager
Public Utility District No. 1 of Chelan County
P.O. Box 1231
Wenatchee, WA 98807-0011

RE: Water Quality Certification
FERC Project No. 2145 - Rocky Reach Pool Raise

Dear Mr. Copp:

This agency certifies that the project described in the August 1991 Application for Amendment of License complies with the applicable provisions of sections 301, 302, 303, 306, and 307 of the Federal Water Pollution Control Act, as amended. This certification is subject to the following provisions:

1. An Oil Spill Prevention, Containment, and Countermeasure Plan must be prepared that covers all oil-filled equipment installed at the site. This equipment includes the turbine/generator set and all oil-filled transformers and capacitors installed at the dam to serve this project.

2. Care must be take to prevent any petroleum products, paint, chemicals, or other harmful materials from entering the water.

3. All construction debris will be disposed of on land so that it cannot enter state water.

4. Work in the waterway will be done so as to minimize turbidity increases.

5. All lumber treated with creosote of other protective material will be completely dry before use in or near the waterway.

6. Concrete will be cured a minimum of seven (7) days before any contact with water.

7. Mobile equipment that enters the water shall be maintained such that a visible sheen from petroleum products shall not appear.

READING FILE COPY

8. Five (5) days advance notice must be given to Ecology before dredging or other work in the waterway commences.

9. A Water Quality Standards Modification must be obtained from Ecology prior to the start of work in the waterway. The plan of work for the portion of the project within the waterway shall accompany the request. The request should also include a copy of the Hydraulics Project Approval secured from the Department of Fisheries or Wildlife for the project, and an explanation of how SEPA has been addressed for the project.

Sincerely,

Robert F. Barwin
Section Manager
Water Quality Program

RFB:JBP:ch
911019.wq

cc: Rod Sakrison, Water Resource - Baran Hall